

**Lee County Board Of County Commissioners
Agenda Item Summary**

Blue Sheet No. 20030893

1. REQUESTED MOTION:

ACTION REQUESTED: Approve award of Project # EX030641 to purchase the following items for Lee County Utilities from Nortrax Equipment Company; one (1) new John Deere 50CZTS Mini Excavator (GSA/non-contract price: \$64,437.58); one (1) new John Deere 270 Skid Steer (Florida State Contract /non-contract price: \$41,584.04); one (1) new John Deere 410G Backhoe Loader (Florida State Contract/non-contract price: \$87,681.97); one (1) new John Deere 230CLC Excavator (Florida State Contract/non-contract price: \$161,079.75); one (1) new John Deere 710G Backhoe Loader (Florida State Contract/non-contract price: \$125,034.80); one (1) new Interstate Trailer 70L BG, Fifth Wheel (Florida State Contract/non-contract price: \$26,247.26); one (1) new Interstate Trailer Model 20DT(non-contract price: \$8499.00); one (1) new Interstate 40DLA Trailer (non-contract price: \$14,795.00); and two (2) new Interstate 14RBS Tag-Along Trailers (non-contract price: \$13,980.00). The above mentioned equipment equals \$543,339.40, grand total.

WHY ACTION IS NECESSARY: Board approval is required as this expenditure will exceed \$50,000.00.

WHAT ACTION ACCOMPLISHES: Provides for the purchase of reliable equipment to perform needed services throughout Lee County.

2. DEPARTMENTAL CATEGORY: 10
COMMISSION DISTRICT # CW

CIOB

3. MEETING DATE:

08-12-2003

4. AGENDA:

- CONSENT
- ADMINISTRATIVE
- APPEALS
- PUBLIC
- WALK ON
- TIME REQUIRED:

5. REQUIREMENT/PURPOSE:
(Specify)

- STATUTE
- ORDINANCE
- ADMIN. CODE AC-4-1
- OTHER

6. REQUESTOR OF INFORMATION:

- A. COMMISSIONER
- B. DEPARTMENT *Utilities*
- C. DIVISION

BY: *Rick Diaz* Director

[Signature]
7/29/03

7. BACKGROUND:

--BACKGROUND BEGINS ON PAGE TWO--

8. MANAGEMENT RECOMMENDATIONS:

9. RECOMMENDED APPROVAL:

A Department Director	B Purchasing or Contracts	C Human Resources	D Other	E County Attorney	F Budget Services				G County Manager
<i>[Signature]</i> 7.30.03	<i>Earl [Signature]</i> 7/29	N/A		<i>[Signature]</i> 7/31/03	OA <i>[Signature]</i> 7-31-03	OM <i>[Signature]</i> 7/31/03	Risk <i>[Signature]</i> 6/31/03	GC <i>[Signature]</i> 7/31/03	<i>[Signature]</i> 7.30.03

10. COMMISSION ACTION:

- APPROVED
- DENIED
- DEFERRED
- OTHER

Rec. by CoAtty
Date: *7/31/03*
Time: *11:45 am*
Forwarded To:
[Signature]
7-31-03 1:05

RECEIVED BY
COUNTY ADMIN: *[Signature]*
7-31-03
1:15
COUNTY ADMIN
FORWARDED TO:
[Signature]
7/31 2:00

--BACKGROUND CONTINUED FROM PAGE ONE--

On July 2, 2003, the Division of Purchasing received a request from Lee County Utilities in conjunction with the Division of Fleet Management to purchase John Deere Equipment from Nortax Equipment Company for a grand total of \$543,339.40.

Section 11.0.3.1 of the Lee County Purchasing and Payment Procedures Manual exempts “the purchase of equipment that has gone through the Administrative Code Procedure, such as State Contracts or Federal General Services Administration Schedules, providing the purchase, rental, or lease amount does not exceed \$50,000.00”. As this expenditure will exceed \$50,000.00, Board approval is required.

Board approval is required as this expenditure exceeds \$50,000.00.

Funds are available: OD5360648700.506430 and OD5366248700.506430

ATTACHMENTS:

- (1) Fleet Managements approval dated July 1, 2003
- (2) Nortax Equipment Company quotations (10 each)



LEE COUNTY

ATTACHMENT /

DIVISION OF FLEET MANAGEMENT

03 JUL -2 AM 11:43

To: Janet Sheehan, Purchasing Director
From: Marilyn Rawlings, Fleet Manager *Bill Moore For MLR*
Date: 7/1/2003
Re: Blue Sheet for the purchase of John Deere Equipment and Accessories.

Please prepare a Blue Sheet as follows for the purchase of one (1) John Deere 50 CZTS mini – Excavator, one (1) John Deere 270 Skid Steer, one (1) John Deere 410 G Backhoe Loader, one (1) John Deere 230CLC Excavator, one (1) John Deere 710 G Backhoe Loader, two (2) Interstate trailers model 14RBS tag-along with beavertail, one (1) Interstate trailer model 40DLA dual axle 40,000 lbs dovetail, one (1) Interstate Trailer, model 20DT, dual axle 20,000 lbs dovetail electric, one (1) Interstate trailer 70LGB, Fifth Wheel, 35 Ton Capacity.

ACTION REQUESTED:

- Approve the purchase of one (1) 2003 John Deere 50 CZTS Mini – Excavator base price \$ 58,196 with contract options and a deduct for government discount in the amount of \$ 53,234.25, approve additional non-contract items in the amount of \$11,203.33 for a total purchase price of \$64,437.58. Approve the purchase of one (1) 2003 John Deere 270 Skid Steer base price \$33,755.04, with additional non-contract options in the amount of \$7,829 for a total of \$41,584.04. Approve the purchase of one (1) 2003 John Deere 410 G (86 Net Horse Power) base price \$44,769.47 contract options in the amount of \$9,429.50, along with non-contract options in the amount of \$33,483.00 for a total purchase price of \$87,681.97. Approve the purchase of one (1) 2003 230CLC Excavator 169 Net Horse Power base price \$132,425.31 with non-contract options in the amount of \$28,654.44, for a total purchase price of \$161,079.75. Approve the purchase of one (1) John Deere 710 G Backhoe Loader base price \$73,274.80 with contract options in the amount of \$13,759.00 with non-contract options in the amount of \$38,001.00 for a total purchase price of \$125,034.80. Approve the purchase of two (2) Interstate trailers Model 14RBS tag-along in the amount of \$6,990. each, total purchase prices \$ 13,980. Approve the purchase of one (1) Interstate Trailer model 20DT dual axle in the amount of \$8,499. Approve the purchase of one (1) interstate Trailer, model 40DLA dual axle dovetail in the amount of \$14,795. Approve the purchase of one (1) Interstate Trailer, 70LGB, fifth wheel, 35 ton capacity in the amount of \$26,247.26.
- Total purchase price for ten (10) pieces of equipment in the amount of \$ 543,339.40.

WHY ACTION IS NECESSARY:

Section 11.0.3.1 of the Lee County Purchasing and Payment Procedures Manual exempts “the purchase of equipment that has gone through the Administrative Code Procedure, such as State Contracts or Federal General Services Administration Schedules, providing the purchase, rental, or lease amount does not exceed \$50,000.” As this expenditure will exceed \$50,000, Board approval is necessary.

WHAT ACTION ACCOMPLISHES:

Fleet Management received a request from the Utilities Department to purchase additional equipment to assist with the ever-increasing growth for service to its customers. The construction department of the Utilities department has become very burdened with requests for new construction. This includes removing and replacing old water lines, installing additional and replacing pumping apparatus, along

ATTACHMENT 2

**Quotation for Lee County Utilities Department
John Deere 410G Backhoe Loader, 93 Net HP
Commodity Code #760-960-110
Florida State Term Contract Number 760-001-03-1
Expires: May 31, 2004**

A. Base Unit Price per State Contract Specifications: (310G)	\$ 32,939.89
Includes:	
Open ROPS Canopy	Mechanical Suspension Seat
Two Wheel Drive	19.5LX24 Rear Tires
11L-16 Front Tires	Master Disconnect Switch
Standard Backhoe Stick	Fire Extinguisher
24" Standard Duty Bucket	1.25 Yard GP Loader Bucket
B. Popular Options Priced On Contract: (Net Prices)	
3001 Mechanical Front Wheel Drive for 410G (9902)	\$ 4,530.00
9902 Upgrade to 410G Model (86 Net HP)	\$ 7,299.58
C. Options @ 50% off Current Manufacturer's List Price:	
1. Upgrade Tires to 21LX24 Rear, 12.5/80-18 Front (4WD Only)	\$ 884.50
2. Extendible Dipperstick Backhoe w/ 5 th Function Valve	\$ 3,432.50
3. Selective Flow Valve for 5 th Function Valve	\$ 1,004.50
4. Auxiliary Plumbing for Extendible Dipperstick	\$ 674.50
5. Add 24" Severe Duty Backhoe Bucket	\$ 681.50
6. Deduct 24" Standard Duty Backhoe Bucket (In Base Price)	-(\$ 482.50)
7. Add 3 rd Function Loader Valve for MP or Grapple Bucket	\$ 582.00
8. Upgrade to 1.32 Yard Multi-Purpose Bucket	\$ 1,375.00
9. 1400 lbs. Front Counterweight	\$ 721.00
10. High Ambient Temperature Cooling Package	\$ 387.00
11. Deluxe Lighting Package (4 Front, 4 Rear & 2 Side)	\$ 139.50
12. 95 Amp Alternator (ROPS units only)	\$ 30.00
D. Additional Dealer Installed Non-Contract Options:	
A. 100 Hour Break-In Service	\$ 600.00
B. SECURE 5 Year / 5000 hour Full Machine Warranty	\$ 5,823.00
C. Indeco MES 1000HD Hydraulic Hammer, Moil Point	\$ 18,250.00
D. Mounting Bracket for Hammer (410G)	\$ 995.00
E. Additional Chisel Point for Hammer	\$ 575.00
F. Backhoe Boom Protection Plate for use with Hammer	\$ 499.00
G. SMART 3,000 hour Preventative Maintenance Contract	\$ 6,491.00
H. 2 Sets of operator's, parts and service manuals & 3 keys	\$ 250.00
Subtotal for additional options (B, C & D):	<u>\$ 54,742.08</u>
Total Price including all options:	\$ 87,681.97
FOB Lee County, FL Fleet Management Division	
Allow 60 days for delivery	

Direct Purchase Orders To:
Eny Sanchez, Governmental Sales
Nortrax Equipment Co. SE LLC
 4343 N.W. 76th Avenue, Miami, FL 33166
 Phone (305) 592-5740 X224 Fax: (305) 513-4353 Cell: (305) 586-2921

Government Sales
4343 N.W. 76th Avenue
Miami, FL 33166
Office: (305) 592-5740 X-224
Fax: (305) 513-4353
Cell: (305) 586-2921



Fax

To: Chevone Peterson	From: Eny Sanchez
Fax: 239-689-7390	Pages: 12
Phone:	Date: 7/23/2003
Re: Deere 410G Price Pages / Quote	CC:

Urgent
 For Review
 Please Confirm
 Please Reply
 Please File

◆ **Comments:**

Chevone,

Fax #3 JD 410G Backhoe info:

Circled items refer to those options listed in section C on our quotation. 50% Discount applies.

Regards,

Eny

PS More faxes on the way.....

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-1

410G BACKHOE LOADER**Equipment for Base Machine****ENGINE:**John Deere PowerTech(TM) 4045T
4.5L (276 Cu. In.)Rated hp: 97 SAE Gross hp / 92
SAE Net hpTurbocharged, Isolation
MountedEngine Coolant -14 Degrees F.
(-17 C)

Coolant Recovery Tank

Sucker-Type Cooling Fan

Vertical Spin-On Engine Oil
FilterOil-to-Water Engine Oil
CoolerSpin-on John Deere Fuel Filter
with Water SeparatorDual Safety Element Dry-Type
Air CleanerMuffler, Underhood, with
Vertical Curved Exhaust Stack
and Non-Spark Arresting

Enclosed Safety Fan Guard

POWERTRAIN:Powershift transmission with
torque converter, Isolation
Mounted to MainframeElectrically actuated twist
grip F-N-R in 1st through 4th
gears.Vertical Spin-on Transmission
FilterPlanetary Final Drives
Differential Lock, foot Switch
Activated

Non-Powered Front Axle

Hydrostatic Power Steering

with Emergency Manual Mode

Power-Assisted, Hydraulic
Service Brakes Inboard, Wet
Disc, Self-Adjusting and
Self-Equalizing (Conforms to
SAE J1473)

Parking/Emergency Brake:

Independent of Service Brakes
(Conforms to SAE J1473)Spring Applied, Hydraulically
Released, Wet Multi-Disc

Transmission Oil Cooler

BACKHOE:

15 Ft. 10 In. Digging Depth

Backhoe Transport Lock Lever

Swing Locking Pin Stored in
Op. StationDeere Two Lever Backhoe
ControlsPin Lock Reversible Stabilizer
FeetIndependent Isolation Mounted
Stabilizer Valve with Two-
Direction Anti-Drift Valves
Less Bucket with Bucket Pins
LOADER:

Return-to-Dig Feature

Bucket Level Indicator

Hydraulic Self-Leveling

Single Lever Control with
Electric Clutch Cut-off
SwitchLess Bucket with Bucket Pins
Loader Boom Service Lock**OPERATOR STATION:**

Modular Design ROPS/FOPS

Canopy Isolation Mounted
with Molded Roof (Conforms to
SAE J1040)

Left and Right Side Access

Slip-Resistant Steps and

Ergonomically Located

Handholds (Conforms to SAE
J105)Non-Suspension Vinyl Seat with
Fore, Aft and Vertical
Adjustment

2 In. (51 mm) Seat Belt

w/Retractors Adjusts

Independent of Seat

Position

Electric Monitor System with

Audible and Visual Warning:

Air Cleaner Restriction

Low Alternator Voltage

Indicator

Engine Coolant Temperature
gauge

Engine Oil Pressure Indicator

Hydraulic Filter Restriction
IndicatorHydraulic Oil Temperature
Display

Park Brake On-Off Indicator

Low Brake Pressure Indicator

Seat Belt Indicator

Torque Converter Temp. gauge

Electric Fuel Gauge,
Illuminated

Electric Hourmeter /

Tachometer / Voltmeter

Key Start Switch with Electric

Fuel Shut-Off

Two (2) Power Ports for
accessories**HORN**

Interior Rearview Mirror

Hand Throttle with Fuel

Economy Setting at 2100 RPM

Suspended Foot Throttle

Built-In Operator's Manual

Storage Compartment with
ManualBuilt-In Beverage and Thermo
Bottle Holder

Coat Hook

Molded Floor Mat

Headliner

LIGHTS:

Two Front Driving/Working and

Two Rear Working Halogen

(35,200 Candlepower Each)

Two Front and Two Rear Turn

Signal/ Flashing

Two Rear Stop and Tail

Two Rear Reflectors

OVERALL VEHICLE:

Two Front and One Rear

Built-In Tie Downs

One-Piece Unitized

Construction Mainframe

Tilt Hood with (2) Service

Positions

Rigid Mounted Front Bumper

Dent Resistant Rear Fenders

19.5 - 24 In. 10 PR (R4) Rear
Tires11L-16 In. 12 PR (F3) Front
TiresRemote Grease Bank for Front
AxleVandal Protection Locking
for:

Engine Access Tilt Hood

Instrument Panel - Lockable

Tool Box - Lockable

Fuel Tank - Lockable

36 Gal. (136L) Fuel Tank

Ground Level Fueling

Reverse Warning Alarm

Switchable to 97 DBA or
111DBA**ELECTRICAL:**

12 Volt System

65 Amp Alternator

Single Battery with 150 Min.

Reserve Capacity and 750CCA

Blade Type Multi-Fused

Circuits

By-Pass Start Safety Cover on
Starter

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-2

410G BACKHOE LOADER
Continued

Positive Terminal Battery Cover	PCLS System	Filter
HYDRAULICS:	Independent Hydraulic Reservoir	"O" Ring Face Seal Connectors
42 GPM Axial Piston Pump - Hydraulic Oil Cooler	10 Micron Vertical Spin-On	Circuit Relief Valve Protection

CODE	DESCRIPTION	LIST PRICE US\$
------	-------------	--------------------

Select One Code From Each Required Category

BASE MACHINE

1770T	410G BACKHOE LOADER	73,021.00
-------	---------------------	-----------

(ROPS)/(FOPS) CANOPY OR CAB

2025	(ROPS)/(FOPS) Canopy with Floor Mat and Headliner NOTE: * Includes 65 amp alternator, molded roof, (2) front halogen driving/work lights and (2) rear halogen work lights (35,200 candlepower each), (2) front and (2) rear turn signal/warning lights, (2) stop and tail lights and (2) rear reflectors.	In Base Price
2050	(ROPS)/(FOPS) Canopy with Front Tinted Safety Glass Windshield and 2-Speed Windshield Wiper NOTE: * Includes 65 amp alternator, molded roof, floor mats and headliner, and (2) front halogen driving/work lights - 35,200 candlepower each. (2) Rear turn signal/warning lights, (2) stop and tail lights and (2) rear reflectors. All right, left and rear canopy features are the same as Code 2025.	1,131.00
2075	Cab with Dual Doors NOTE: * Includes 65 amp alternator, tinted safety glass, molded roof, deluxe interior trim, floor mat, head liner, 3-speed 40,000 BTU fresh air intake heater, defroster and pressurizer, (2) front halogen driving/work lights and (2) rear halogen work lights (35,200 candlepower each), (2) front and (2) rear turn signal/warning lights, (2) stop and tail lights, (2) rear reflectors, (2) front 2-speed, and (1) rear 1-speed wiper.	6,368.00
2085	Cab with Dual Doors and Air Conditioning NOTE: * Same as Code 2075 plus 4-speed 40,000 BTU air conditioner. * CFC free R134a * Includes high ambient temperature cooling package. * Includes 85-amp alternator.	8,455.00

SEAT

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-3

410G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
	SEAT	
Continued		
2615	Non-Suspension, Vinyl, Swivel Seat without Arm Rests NOTE: * Includes 2 in. retractable seat belt.	In Base Price
2625	Mechanical Suspension Deluxe, Vinyl, Swivel Seat with Lumbar Adjustment and Arm Rests, Fully Adjustable NOTE: * Includes 2 in. retractable seat belt.	562.00
2635	Air Suspension Deluxe, Vinyl, Swivel Seat with Lumbar Adjustment and Arm Rests, Fully Adjustable NOTE: * Includes 2 in. retractable seat belt. * Requires Code 9055, Tilt Steering Wheel.	672.00
2675	Mechanical Suspension Deluxe, Fabric, Swivel Seat with Lumbar Adjustment and Arm Rests, Fully Adjustable NOTE: * Recommended for use with Code 2075, 2080 or 2085, Cab. * Includes 2 in. retractable seat belt.	562.00
2685	Air Suspension Deluxe, Fabric, Swivel Seat with Lumbar Adjustment and Arm Rests, Fully Adjustable NOTE: * Includes 2 in. retractable seat belt. * Recommended for use with Code 2075, 2080 or 2085, Cab. * Requires code 9055, Tilt Steering Wheel.	672.00

FRONT AXLE AND TRANSMISSION

3035	Two Wheel Drive (2WD) with Powershift Transmission NOTE: * Includes torque converter with electrically actuated twist grip F-N-R in 1st through 4th gears.	In Base Price
3085	Four Wheel Drive (4WD) with Front Wheel Limited Slip Differential and Powershift Transmission NOTE: * Includes drive shaft guard on main frame. * Four-wheel drive on/off indicator illuminated. * Includes torque converter with electrically actuated twist grip F-N-R in 1st through 4th gears.	8,405.00

TIRES AND WHEELS (FRONT AND REAR)

4270	FOR USE WITH TWO WHEEL DRIVE Goodyear 19.5 - 24 in. 10 PR (R4) Tubeless Rear & 11L - 18 in. 12 PR (F3) Front Tires NOTE: * 86 in. (2.18 m) overall width. * Requires Code 3025, 3035 2WD. * Rear tire chains require wheel spacers	In Base Price
------	---	---------------

1 December 2000

US

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-4

410G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
TIRES AND WHEELS (FRONT AND REAR)		
Continued		
4271	Firestone 19.5 - 24 In. 10 PR (R4) Tubeless Rear & 11L - 18 In. 12 PR (F3) Front Tires NOTE: * 86 In. (2.18 m) overall width. * Requires Code 3025, 3035 2WD. * Rear tire chains require wheel spacers	No Charge
4360	Goodyear 21L - 24In. 10PR (R4) Tubeless Rear & 14.5/75 - 18 In. 10PR (F3) Front Tires NOTE: * 92 In. (2.34 m) overall width. * Requires Code 3025, 3035 2WD. * Rear tire chains require wheel spacers	1,108.00
4361	Firestone 21L - 24In. 10PR (R4) Tubeless Rear & 14.5/75 - 18 In. 10PR (F3) Front Tires NOTE: * 92 In. (2.34 m) overall width. * Requires Code 3025, 3035 2WD. * Rear tire chains require wheel spacers	1,108.00
FOR USE WITH FOUR WHEEL DRIVE		
4790	Goodyear 19.5L - 24 In. 10 PR (R4) Tubeless Rear & 12.5/80 - 18 In. 10 PR Traction Front Sure Grip Lug Tires NOTE: * 86 In. (2.18 m) overall width. * Requires Code 3075, 3085 4 Wheel Drive. * Rear tire chains require wheel spacers.	758.00
4791	Firestone 19.5L - 24 In. 10 PR (R4) Tubeless Rear & 12.5/80 - 18 In. 10 PR Traction Front Sure Grip Lug Tires NOTE: * 86 In. (2.18 m) overall width. * Requires Code 3075, 3085 4 Wheel Drive. * Rear tire chains require wheel spacers.	758.00
4890	Goodyear 21L - 24 In. 10 PR (R4) Tubeless Rear & 12.5/80 - 18 In. 10 PR Traction Front Sure Grip Lug Tires NOTE: * 92 In. (2.34 m) overall width. * Requires Code 3075, 3085 4 Wheel Drive. * Rear tire chains require wheel spacers.	1,789.00
4891	Firestone 21L - 24 In. 10 PR (R4) Tubeless Rear & 12.5/80 - 18 In. 10 PR Traction Front Sure Grip Lug Tires NOTE: * 92 In. (2.34 m) overall width. * Requires Code 3075, 3085 4 Wheel Drive. * Rear tire chains require wheel spacers.	1,789.00

option #1

BACKHOE

5025	Standard Dipperstick	In Base Price
5075	Extendible Dipperstick NOTE: * Cannot be used with Code 5110, Four Function Valve.	8,483.00

option #2 USE with 5120

BACKHOE VALVES

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-5

410G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
BACKHOE VALVES		

Continued

NOTE:

Refer to Additional Available Equipment for complete information when installing hydraulic backhoe attachments.

5110

Four Function Valve

In Base Price

NOTE:

* Requires Code 5025, Standard Dipperstick.

5120

Five Function Control Valve

402.00

NOTE:

* If Equipped With 5025, Standard Dipperstick, fifth valve section can operate: Field installed extendible dipperstick OR

Thumb, swingers or jaw buckets
* Fifth valve section work ports plugged, without circuit reliefs, with right pedal.

* If Equipped With 5075, Extendible Dipperstick, fifth valve section operates extendible dipperstick.

USE WITH 5075

5130

Five Function Valve Plus Selective Flow Valve (9, 13 and Variable from 13 to 34 GPM), 1000-3000 PSI Adjustable

2,008.00

NOTE:

* Factory setting at 25 GPM.

* Includes a side console switch to activate the selective flow valve section and foot switch to control attachment on/off.

* Fifth valve section work ports plugged without circuit reliefs, with right pedal or lever control.

* Selective flow valve section with work port plugged, with controls.

* Codes 5330 and 5350 provide plumbing from selective flow control valve to end of Dipperstick.

* If equipped with 5025, Standard Dipperstick, fifth valve section can operate cylinder-actuated attachments.

* If equipped with 5075, Extendible Dipperstick, fifth valve section operates extendible dipperstick.

* Selective flow valve can operate low or high flow motor attachments.

OPTION #3

5140

Six Function Manual Control Valve

1,891.00

NOTE:

* Includes fifth and sixth valve section with work ports plugged without circuit reliefs. Includes left pedal.

* Also order AT194368, Attachment Hydraulic Plumbing Kit for Thumb, Clamp, Swinger or Jaw Bucket.

* If equipped with code 5025, Standard Dipperstick, fifth and/or sixth valve section operates cylinder actuated attachments.

* If equipped with code 5075, Extendible Dipperstick:

- Fifth valve section operates extendible dipperstick.

- Sixth valve section operates cylinder actuated attachments.

1 December 2000

US

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-6

410G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE U.S. \$
BACKHOE VALVES		
Continued		
5150	Five Function Control Valve Plus Selective Flow Valve (9, 13, and Variable from 13 to 34 GPM) 1000-3000 PSI Adjustable NOTE: * Factory setting at 25 GPM. * Includes a side console switch to activate the selective flow valve section and foot switch to control attachment orbit. * Includes fifth and sixth valve section with work ports plugged without circuit reliefs. Includes left pedal. * Selective flow valve section with work port plugged with controls. * Codes 5330 or 5350 provide auxiliary plumbing from selective flow valve to end of Dipperstick. * If equipped with Code 5025, Standard Dipperstick, fifth and/or sixth valve section operates cylinder-actuated attachments. * If equipped with Code 5075, Extendible Dipperstick: - Fifth valve section operates Extendible Dipperstick. - Sixth valve section operates cylinder actuated attachments. * Selective flow valve can operate low or high flow motor attachments	2,740.00
BACKHOE CONTROLS		
5225	Deere Two Lever Controls (Standard Backhoe or Extendible Dipperstick) NOTE: * Includes all Controls.	In Base Price
5245	Case Three Lever Controls with Foot Swing (Standard Backhoe or Extendible Dipperstick) NOTE: * Includes all Controls. * Requires Code 5110, 5120 or 5130 Backhoe Valve.	484.00
5285	SAE Excavator Style Two Lever Controls NOTE: * Includes all Controls.	173.00
BACKHOE AUXILIARY PLUMBING		
5310	Less Backhoe Auxiliary Plumbing	In Base Price
5330	Standard Dipperstick Auxiliary Plumbing for Five Function Valve Plus Selective Flow Valve NOTE: * Requires Code 5025, Standard Dipperstick, and Code 5130 or 5150, Flow Control Valve. * Includes hydraulic lines from the selective flow valve section to end of dipperstick. * Required for hammers, compactors, high or low flow motor attachments mounted to end of dipperstick	1,143.00
5350	Extendible Dipperstick Auxiliary Plumbing for Five Function Valve Plus Selective Flow Valve NOTE: * Requires Code 5075, Extendible Dipperstick, and Code 5130 or 5150, Flow Control Valve. * Includes hydraulic lines from the selective flow valve section to end of dipperstick. * Required for hammers, compactors, high or low flow motor attachments mounted to end of dipperstick	1,348.00

OPTION
4

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-7

410G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
------	-------------	---------------------

BACKHOE BUCKETS

NOTE:

- * All buckets include lift holes.
- * Fangs teeth are standard on HD buckets.
- * Fabricated teeth are standard on regular buckets.

5600	Less Backhoe Bucket with Bucket Pins	In Base Price
5616	12" (305 mm) Wide - HD - 3.3 Cu. Ft. (0.09 Cu. M.) Capacity	743.00
5626	18" (457 mm) Wide - HD - 5.1 Cu. Ft. (0.14 Cu. M.) Capacity	856.00
5628	18" (457 mm) Wide - Severe Duty - 5.1 Cu. Ft. (0.14 Cu. M.) Capacity	1,035.00
5654	24" (610 mm) Wide - Regular - 7.5 Cu. Ft. (0.21 Cu. M.) Capacity	965.00
5656	24" (610 mm) Wide - HD - 7.5 Cu. Ft. (0.21 Cu. M.) Capacity	1,009.00
5658	24" (610 mm) Wide - Severe Duty - 7.5 Cu. Ft. (0.21 Cu. M.) Capacity	1,186.00
5678	24" (610 mm) Wide - HD - 8.8 Cu. Ft. (0.25 Cu. M.) Capacity	1,192.00
5678	24" (610 mm) Wide - Severe Duty - 8.8 Cu. Ft. (0.25 Cu. M.) Capacity	1,363.00
5688	30" (762 mm) Wide - HD - 10 Cu. Ft. (0.28 Cu. M.) Capacity	1,132.00

LOADER HYDRAULICS

7025	Two Function Valve and Lines with Single Control Lever	In Base Price
7075	Three Function Valve and Lines with Dual Lever Controls NOTE: * For multi-purpose bucket and front attachments. * Includes valve with circuit relief and .5 in. (12.7 mm) hoses and steel lines to loader cross tube.	1,164.00

LOADER BUCKETS (NOT FOR USE WITH COUPLER)

7800	Less Loader Bucket with Pins for Buckets or Front Attachments	In Base Price
------	---	---------------

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-8

410G BACKHOE LOADER

Continued

CODE DESCRIPTION LIST PRICE US \$

LOADER BUCKETS (NOT FOR USE WITH COUPLER)

Continued

7840 *OPTION #8* 1.25 Cu. Yd. (.98 Cu. M.) Heavy Duty Long Lip Bucket *DEDUCT FROM 7685* 2,000.00
 NOTE:
 * 86 in. (2.18 m) wide.
 * Punched for bolt-on cutting edge. For cutting edge, order T150517 and appropriate attaching hardware from parts.
 * Includes two lift holes.

7845 1.3 Cu. Yd. (1.0 Cu. M.) Heavy Duty Long Lip Bucket 2,290.00
 NOTE:
 * 82 in. (2.34 m) wide.
 * Includes reversible bolt-on cutting edge and skid plates.
 * Includes two lift holes.

7855 1.5 Cu. Yd. (1.15 Cu. M.) Heavy Duty Long Lip Bucket 2,500.00
 NOTE:
 * 82 in. (2.34 m) wide.
 * Includes reversible bolt-on cutting edge and skid plates.
 * Includes two lift holes.

7885 *OPTION #8* 1.32 Cu. Yd. (.98 Cu. M.) Multi-Purpose Bucket 4,750.00
 NOTE:
 * Requires Code 7075, Aux. Loader Hydraulics.
 * 82 in. (2.34 m) bucket width.
 * Includes reversible bolt-on cutting edge and skid plates.
 * Pre-drilled for eight teeth. Order teeth from parts.
 * Includes two lift holes. *#2,750. NET DIFF.*

FRONT COUNTERWEIGHTS

NOTE:
 See following Counterweight Selection Chart for appropriate combination of counterweights.

8410 Front Bumper - 30 Lb. (14 kg.) In Base Price

8425 400 Lb. (181 kg) Front Counterweight 412.00
 NOTE:
 * (3) additional T165739, 250 Lb. Front Counterweights may be added to a maximum of 1150 lb. (522 kg).

8455 650 Lb. (295 kg) Front Counterweight 670.00
 NOTE:
 * (3) additional T165739, 250 Lb. (113 kg) Front Counterweights may be added to a maximum of 1400 lb. (635 kg).

8475 900 Lb. (408 kg) Front Counterweight 927.00
 NOTE:
 * Includes (1) 650 lb. (295 kg) counterweight and (1) T165739, 250 Lb. (113 kg) Counterweight.
 * (2) additional T165739, 250 Lb. (113 kg) Front Counterweights may be added to a maximum of 1400 lb. (635 kg).

8485 1150 Lb. (522 kg) Front Counterweight 1,185.00
 NOTE:
 * Includes (1) 650 lb. (295 kg) counterweight and (2) T165739, 250 Lb. (113 kg) Counterweights.
 * (1) additional T165739, 250 Lb. (113 kg) Front Counterweight may be added to a maximum of 1400 lb. (635 kg).

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-9

410G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
------	-------------	---------------------

FRONT COUNTERWEIGHTS

Continued

8485	1400 Lb. (635 kg) Front Counterweight NOTE: * Includes (1) 650 lb. (295 kg) counterweight and (3) T145739, 250 Lb. (113 kg) Counterweights.	1,442.00
------	--	----------

BATTERY

8625	Single Battery, 150 Minute Reserve Capacity (750 CCA)	in Base Price
8675	Dual Batteries, 300 Minute Reserve Capacity (1500 CCA) NOTE: * Recommended in temperatures below 32 degrees F (0 degree C).	185.00

SPECIAL EQUIPMENT - ORDER AS DESIRED

MISCELLANEOUS

9025	John Deere Backhoe Bucket Coupler NOTE: * Fits 300 Series SE & SG as well as 410E & G. * Will not fit Case, Cat or other series John Deere buckets. * Proper counterweighting is required. See Counterweight Selection Chart. * Recommend Backhoe Boom Bolt-on Protection Plate.	683.00
9030	Universal Backhoe Bucket Coupler NOTE: * Fits John Deere 310SE, 410E, 300D-510D buckets. * Fits Case K and L Series and Cat B and C Series Buckets. * Recommend 300D-510D and 210C-510C buckets, use high strength pins: -AT18134A, Pin for 12 Inch Buckets -AT179130, Pin for 18-36 Inch Buckets * Proper counterweighting is required. See Counterweight Selection Chart. * Recommend Backhoe Boom Bolt-on Protection Plate.	978.00
9045	Chrome Exhaust Extension	98.00
9050	High Ambient Temperature Cooling Package NOTE: * Recommended for ambient temperatures above 110 degrees F (43 degrees C), and/or field installed air conditioning. * Included in Code 2065, Cab with Air Conditioning.	774.00
9055	Tilt Steering Wheel	417.00
9065	Deluxe Lighting Package NOTE: * Additional two (2) front, (2) rear additional Halogen Work Lights and (2) side docking lights for Cab * 35,200 candlepower each. * Requires Code 9060, 95 Amp Alternator, except when ordered with Code 2065, Cab with Air.	279.00
9070	AM-FM Stereo Weather Band Radio with Digital Clock for Cab NOTE: * Requires Code 2075 or 2085 Cab.	521.00

1 December 2000

US

Updated 05/08/02

UTILITY PRODUCTS

U-5-410G-10

410G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
9080	110 Volt Engine Coolant Heater (1000 Watts) NOTE: * Recommended in temperatures below 32 degrees F (0 degrees C).	62.00
9085	Electric Ether Start Aid NOTE: * Recommended in temperatures below 32 degrees F (0 degrees C).	139.00
9090	95 Amp Alternator NOTE: * Required with Code 9085, Additional Cab Lights. * Not required if equipped with Code 2085, Cab with Air.	60.00
9110	Ride Control NOTE: * Activated by on/off rocker switch on the right console.	998.00
9131	Single Battery Disconnect (UPDATED 03-27-02) NOTE: * Requires Code 8625 * Using disconnect will remove clock settings.	98.00
9132	Dual Battery Disconnect (UPDATED 03-27-02) NOTE: * Requires Code 8675 * Using disconnect will remove clock settings.	98.00
9150	Floor Heater for ROPS NOTE: * Requires Code 2025, ROPS or 2050, Canopy w/Windshield	712.00
9175	Front Windshield Washer NOTE: * Requires Code 2075 or 2085, Cab.	170.00
9225	3 In. Retractable Seat Belt	73.00
9460	Spanish Trademarks and Decals	No Charge
9470	French Trademarks and Decals	No Charge

DEALER-INSTALLED ATTACHMENTS

NOTE:
* The following items can be installed by the Dealer, or contact JRB Custom Works for pricing and installation prior to shipping complete unit from the Dubuque Factory.
* Prices listed below are for kit material only.

AT185522	LOADER BUCKETS 1.25 Cu. Yd. (.98 Cu. M.) Heavy Duty Long Lip Bucket NOTE: * 68 in. (2.18 m) wide. * Punched for bolt-on cutting edge. For cutting edge, order T150517 and appropriate attaching hardware from parts. * Includes slid plates and two lift holes.	2,000.00
----------	---	----------

1 December 2000
US

Construction/Industrial Equipment and Forklifts

760-001-03-1

Effective: 10/30/2002 through 5/31/2004

Certification
Legal Information
Exhibit A - General Specifications
Exhibit B - Price Sheets
Ordering Instructions
Sample Purchase Order
Revisions
Complete Contract

760-960-110
(66)

MAKE JOHN DEERE

CONTRACTOR	MODEL	*DISCOUNT F.O.B. CONTRACTOR	PRICE
NORTRAX EQUIPMENT	310G	\$260.00	\$32,939.89 (25)

1. Percentage discount off Manufacturer's current published retail prices for all specified Options for a State of Florida Base Unit and any Optional models bid. (The percentage discount is applied to the Manufacturer's current published retail prices.)

50% Discount

**Date of current published retail price book: 05/08/02

*Discount for pickup by ordering agency at Contractor's place of business.

**NOTE: ALL DATES MUST BE FOR THE CURRENT PUBLISHED RETAIL PRICE BOOK.

Approximate delivery time required after receipt of order: 45-60 DAYS

OPTION CODING: 760-960-111-Option Number, Tractor-Loader-Backhoe, Industrial, 62 HP, Spec. 66

OPTIONS:

(1) 1001. High efficiency bypass oil purification system. This system is designed to reduce or eliminate engine oil changes and extend its useful life. The Puradyn Oil Filtration System or approved equivalent. Puradyn Filter Technologies, Inc. 1-800-488-0577.

PRICE: \$758.35

(2) 3001. Mechanical front wheel drive (FWD) for the base model, Option 9901, 9902 and 9903. Note to bidder: Provide only a price difference between the base model, Option 9901, 9902 and 9903.

(BASE) PRICE: \$4,045.00
 (OPT 9901) PRICE: \$4,118.00
 (OPT 9902) PRICE: \$4,530.00
 (OPT 9903) PRICE: \$6,900.00

(3) 4001. High efficiency bypass oil purification system. This system is designed to reduce or eliminate hydraulic oil changes and extend its useful life. The Puradyn Oil Filtration System or approved equivalent. Puradyn Filter Technologies, Inc. 1-800-488-0577.

PRICE: \$915.85

(4) 4002. Automatic lubrication system. System shall consist of an electronically operated pump delivering fluid grease of NLGI grades 000 and 00 to adjustable piston distributors that can meter the amount of grease to each lubrication point. Vogel

Automatic Lubrication System or approved equivalent. Vogel Automatic Lubrication, Inc., (757) 380-8585, email: vogel@vogel-lube.com.

PRICE: \$4,700.00

- (5) 5002. Fully enclosed, sound controlled ROPS cab, factory installed, with heater, defroster, front windshield wiper(s), rearview mirror(s), tinted safety glass and lockable doors.

PRICE: \$3,161.00

- (6) 5003. Air conditioning for Option 5002.

PRICE: \$1,025.00

- (7) 8001. Special state color, DOT Yellow, Federal Yellow No. 13538, DuPont #L9069A, ACME No. 2712, Deere No. PT102, or approved equivalent, (may be Contractor painted if factory painting is not available). NOTE: The entire unit, including Options, shall be painted the same color.

PRICE: \$2,500.00

- (8) 9901. 80 SAE Net HP model, minimum. Unit shall be of the same Manufacturer. Model bid shall meet or exceed all other minimum requirements and features as the base model bid. Note to bidder: Provide only a price difference between the base model and model bid.

MODEL: 310SG

SAE NET HP: 84

LOADER PERFORMANCE

LOADER LIFT CAPACITY:
6,247 LBS

LOADER BUCKET CAPACITY:
1.2 CU YD

BACKHOE PERFORMANCE

MAX. DIGGING DEPTH (standard stick): 14'6"

PRICE: \$2,741.00

- (9) 9902. 90 SAE Net HP model, minimum. Unit shall be of the same Manufacturer. Model bid shall meet or exceed all other minimum requirements and features as the base model bid. Note to bidder: Provide only a price difference between the base model and model bid.

MODEL: 410G

SAE NET HP: 92

LOADER PERFORMANCE

LOADER LIFT CAPACITY:
7,340 LBS

LOADER BUCKET CAPACITY:
1.25 CU YD

BACKHOE PERFORMANCE

MAX. DIGGING DEPTH (standard stick): 15'10"

PRICE: \$7,299.58

- (10) 9903. 99 SAE Net HP model, minimum. Unit shall be of the same Manufacturer. Model bid shall meet or exceed all other minimum requirements and features as the base model bid. Note to bidder: Provide only a price difference between the base model and model bid.

MODEL: 710D

SAE NET HP: 115

LOADER PERFORMANCE

LOADER LIFT CAPACITY:

7
733 LBS

LOADER BUCKET CAPACITY:

1.62 CU YD

BACKHOE PERFORMANCE

MAX. DIGGING DEPTH (standard stick): 18'2"

PRICE: \$40,334.91



**Quotation for Lee County Utilities Department
John Deere 50CZTS Mini-Excavator
Per GSA Contract Pricing #GS-30F-1021D**

Nortrax Equipment Co. is pleased to quote you the following equipment:

A. Equipment / Options on contract:

(1) One NEW 2003 John Deere 50CZTS Mini-Excavator	\$ 58,196.00
Includes: All standard equipment and features plus:	
3125 16" Rubber Tracks	In Base Price
8150 TOPS / FOPS Canopy	In Base Price
AT280191 Deere Worksite Pro HB75 Hydraulic Hammer	\$ 11,187.00
AT189215 Quick Coupler Adapter for Hammer	\$ 420.00
AT189230 18" Heavy Duty Bucket, 3 Teeth	<u>\$ 912.00</u>
	Total List Price: \$ 70,715.00
	Less 24.72% off Governmental Discount: <u>-\$ 17,480.75</u>
	Subtotal Net Price: Base Machine \$ 53,234.25

B. Additional Dealer Installed Non-Contract Options:

A. 100 Hour Break-In Service	\$ 500.00
B. SECURE 5 Year/5000 Hour Full Machine Warranty	\$ 3,794.00
C. Chisel Point Hammer Tool	\$ 433.00
D. Asphalt Cutter Hammer Tool	\$ 1,070.33
E. SMART 3,000 hours Preventative Maintenance Contract	\$ 5,156.00
F. 2 Sets of Operator, Parts and Service Manuals & 3 keys	<u>\$ 250.00</u>
Subtotal for additional options (A-F):	\$ 11,203.33

Total Price including all options: **\$ 64,437.58**
 FOB Lee County, FL Fleet Management Division
 Allow 60 days for delivery

Direct Purchase Orders To:
 Eny Sanchez, Governmental Sales
 Nortrax Equipment Co. SE LLC
 4343 N.W. 76th Avenue, Miami, FL 33166
 Phone (305) 592-5740 X-224 Fax: (305) 513-4353 Cell: (305) 586-2921

GENERAL SERVICES ADMINISTRATION
OFFICE OF FEDERAL SUPPLY AND SERVICES

Authorized Federal Supply Schedule Price List (Catalog)

Machinery Listed: Backhoe Loaders, Dozers, Wheel Loaders,
 Motorgraders, Excavators and Crawler Loaders

Manufacturer Name: John Deere Construction Equipment Co.

FSC Class – 2410, 3805

Contract Number: GS-30F-1021D

Contract Period: 1 October 2000 through 29 September 2005

Delivering Dealer and Warranty Service Centers:

Nortrax Equipment Co.
4343 N.W. 76th Avenue
Miami, FL 33166

Nortrax Equipment Co.
2611 Hammondville Rd.
Pompano Beach, FL 33069

Nortrax Equipment Co.
3933 Beeline Highway
West Palm Beach, FL 33404

Nortrax Equipment Co.
2995 Hanson Street
Ft. Myers, FL 33916

Nortrax Equipment Co.
4333 John Young Parkway
Orlando, FL 32804

Nortrax Equipment Co.
5102 N. 56th Street
Tampa, FL 33610

Contact Information: Bob Rainey
 Government Sales Mgr., Central Florida
 (813) 621-4902

 Eny Sanchez
 Government Sales, South Florida
 (888) 235-6333

Federal ID # 58-2507812

Configurator - View Summary

... 50C ZTS COMPACT EXCAVATOR

Configured Price:
\$70,715.00

Price and availability subject to change without notice.
 Prices in US Dollars. Taxes, extended warranty and freight charges are extra. Some additional charges may apply.

Jul 22, 2003 9:40:38 AM CDT

Configured Features- Required

BASE MACHINE \$58,196.00
 1400FF 50C ZTS COMPACT EXCAVATOR

TRACK In Base Price
 3125 400 MM (16 In.) Rubber Track

CANOPY OR CAB In Base Price
 8150 TOPS/FOPS Canopy

Configured Features- Accessory

Qty	Code	Description	Price
1	AT280191	Model HB75 Hydraulic Hammer	\$11,187.00

- Installation instructions T184976.
- 750-foot pound class hammer.
- Includes all hoses and hydraulic quick couplers.
- Requires Quick Coupler Interface Adapter to mount on mechanical quick coupler.
- Requires canopy or cab screen, front protection. See G.R. Manufacturing Referral Attachments.
- Includes KV17887 Moil Point.

1	KV18177	Chisel Point Breaker Tool	See Parts
1	KV17891	Asphalt Cutter	See Parts
1	AT189215	Quick Coupler Interface Adapter	\$420.00

NOTE:
 * Required to adapt hammer or auger for mechanical quick coupler use.

1	AT189230	18 In. (457 mm) Heavy Duty Bucket; 3.6 Cu. Ft. (0.10 Cu. M) (3 Teeth Included)	\$912.00
---	----------	--	----------

Preliminary Price:	\$70,715.00
Discount :	-\$0.00
Sub Total:	\$70,715.00
Referral Attachment Total:	+\$0.00
Configured Price:	\$70,715.00

TOTAL LIST PRICE \$70,715.00

Configurator - View Summary

Configured Price:	\$70,715.00
Freight:	\$0.00
Setup & Delivery:	\$0.00
Discounts:	\$0.00
Trade In Allowance:	\$0.00
Extended Warranty:	\$0.00
Taxes:	\$0.00
Total Delivered Price:	\$70,715.00



[PRIVACY](#) [LEGAL](#)

**TEMPORARY PRICE REDUCTION DISCOUNTS
EXPIRES 30 September 2002**

DISCOUNTS FROM LIST		
MACHINE MODEL	DISCOUNT FROM LIST	REVISED DISCOUNT FROM LIST
310G	38.94	39.94
310SG	38.94	39.94
410G	38.94	39.94
710D	36.97	37.97
450H	27.52	28.52
550H	27.52	28.52
650H	27.52	28.52
700H	27.52	28.52
750C	28.52	29.52
750C LGP	28.52	29.52
304H	30.71	31.71
324H	30.71	31.71
344H	30.71	31.71
444H	34.24	35.24
TC44H	34.24	35.24
544H	35.66	36.66
TC54H	35.66	36.66
624H	35.66	36.66
644H	35.66	36.66
670C-II	37.75	38.75
670CH-II	37.75	38.75
672CH-II	37.75	38.75
770C-II	40.03	41.03
770CH-II	40.03	41.03
772CH-II	40.03	41.03
272TS	23.72	24.72
352TS	23.72	24.72
502TS	23.72	24.72
80	32.12	33.12
120	32.12	33.12
160LC	30.71	31.71
200C LC	30.71	31.71
230C LC	30.71	31.71
240	28.00	
250	28.00	
260	28.00	
270	28.00	
280	28.00	



Government Sales
4343 N.W. 76th Avenue
Miami, FL 33186
Office: (305) 592-5740 X-224
Fax: (305) 513-4353
Cell: (305) 586-2921



Fax

To: Chevone Peterson **From:** Eny Sanchez

Fax: 239-689-7390 **Pages:** 6

Phone: **Date:** 7/23/2003

Re: Deere 50CZTS Mini-Excavator Contract **CC:**

Urgent For Review Please Confirm Please Reply Please File

• **Comments:**

Chevone,

Fax #2 50CZTS info:

Note that the 50CZTS is the replacement for the 50ZTS with the introduction of the C-series just like the 230CLC Excavator.

Regards,

Eny

PS More faxes on the way.....



For: Lee County Utilities
John Deere 270 Skid Steer
Commodity Code #760-460-100
Florida State Term Contract Number 760-001-03-1
Expires: May 31, 2004

A. Base Unit per State Contract Specifications:**\$ 23,714.96**

Includes the following options:

1. 2070 Beefy Baby Tires, 12-16.5
2. 3001 Hydraulic Self-leveling bucket
3. 8040 Backup Alarm
4. 8075 Dual Flashers
5. 8181 Suspension Seat
6. 8210 Horn
7. KV11751 SMV Emblem
8. 5 lb. Fire Extinguisher
9. 19.4 C.F. Construction Bucket

B. Options Priced On Contract: (Net Prices) None**C. Additional Contract Options @ Manufacturer's Published List Price**

A. Deduct 2070 Beefy Baby Tires, 12-16.5	+	\$ 556.00 ***
--	---	---------------

*** List Price is negative (-556.00) so a deduct of a negative amount turns into a positive or a net add of \$556.00.

B. Add 2180 14 X 17.5 14PR Galaxy "Beefy Baby II" Tires	+	\$ 706.00
C. 8070 Demolition Door Kit	+	\$ 944.00
D. Add 8130 Rear Weight Bracket Kit	+	\$ 175.00
E. Add Eight (8) R66969Y 44lb. Rear Weights (\$32.00 each)	+	\$ 256.00
F. Deduct 19.4 C.F. Construction Bucket	-	\$ 722.37
G. Add MP78 78" Multi-Purpose Bucket	+	\$ 2,599.00
H. Add PF48 48" Pallet Forks	+	\$ 855.00
I. Add PB84 84" Pickup Broom	+	\$ 5,399.00
J. Add 14" Steel Tracks for tires with Track Guard Kit	+	\$ 3,099.00
Total List Price of Options:		\$ 13,866.63
Less 28% State Contract Discount for options:		-\$ 3,882.65
Total Net Price of Contract Options:		\$ 9,983.98 \$ 9,983.98

D. Additional Dealer Installed Non-Contract Options: (Net Prices)

• 2 Sets of Service and Parts Manuals	\$ 250.00	\$ 250.00
• Secure 60 month/5000 hour Power Train Ext. Warranty	\$ 2,257.00	\$ 2,257.00
• SMART 3000 hours PM contract	\$ 4,847.00	\$ 4,847.00
• 100 Hour Break In Service	\$ 475.00	\$ 475.00

Total Net Price of Machine with all options included:**\$ 41,527.94****Tax Exempt FOB Lee County, FL**

Direct Purchase Orders To:
Eny Sanchez, Government Sales
Nortrax Equipment Co. SE LLC
4343 N.W. 78th Avenue, Miami, FL 33166
Phone (305) 592-5740 Fax (305) 513-4353 Cell (305) 586-2921

**JOHN DEERE COMMERCIAL WORKSITE PRODUCTS
SKID STEERS**

**270 SKID STEER
Equipment for Base Machine**

<p>Engine: John Deere 4045D Four Cylinder Naturally Aspirated 82 Gross H.P. 77 Net H.P. Dry Type Dual Element Air Cleaner Anti-Freeze Solution to -34F 20 Gallon (76 L) Fuel Tank</p> <p>Drive System and Brake: Hydrostatic Pumps Four Wheel Drive Two 100 HZ Endless Chain Final Drive Integral Automatic Wet-Disk Brake Spring Applied Hydraulic Released</p> <p>Gauges and Instruments: Fuel Gauge Hourmeter Battery Voltage Engine Oil Pressure Water Temperature Automatic Engine Shutdown with Alarm Automatic Engine Start Preheat</p> <p>Electrical:</p>	<p>12-Volt Electrical Battery With 950 Cold Cranking Amps Alternator 55 Amp Lights, Front and Rear</p> <p>Hydraulics: 3-Spool Open Center Valve 21.3 gpm (80.6 lpm) Pump John Deere Boom and Bucket Cylinders Cushioned Down Boom Cylinders Auxiliary Hydraulics with Flat Faced Couplers Loader Arm & Tilt Function Lockout System Loader Lockout Override</p> <p>Performance Characteristics: SAE J818 Rated Operating Capacity - 2800 lb. (1270 kg) SAE Tipping Load 5600 lb. (2540 kg) SAE Bucket Breakout Force 10,500 lb. (4773 kg) SAE Boom Breakout Force 4800 lbs. (2182 kg) Axle Torque 5749 lbs-ft (7795 Nm) Dump Reach 32 In. (813 mm)</p>	<p>with Foundry Bucket Quik-Tatch Mounting</p> <p>Operator Protection/Comfort: FOPS / ROPS Roll-Gard Canopy with Side Screens Single Lever Boom Arm Lock in Cab Retractable Seat Belt with Holder Operator Presence System (Seat Switch & Seat Belt Interlocks with Brake, Boom, and Bucket Circuits) Four Full Length Grab Handles for Easy Entry / Exit Rear Cab Window Deluxe Seat Comfort Armrests "Patent Pending" Foot Controls</p> <p>Tires: Four 14x17.5 12 PR SKS Extra-Wall Tires 12 in. and 14 in. Tires Shipped @ Wide Setting</p> <p>John Deere Standard Warranty 1 Year Unlimited Hours</p>
---	--	---

CODE	ATTACHMENT DESCRIPTION IDENTIFIER	WEIGHT LBS.	REF.	LIST PRICE US\$
------	-----------------------------------	-------------	------	-----------------

Select One Code From Each Required Category

BASE MACHINE

F.O.B. Dubuque, Iowa

2450T	270 SKID STEER	842K4592	32,350.00
-------	----------------	----------	-----------

TRANSMISSION

1025	Single-Speed		In Base Price
1050	Two-Speed	401K550	2,040.00

WHEELS AND TIRES

**JOHN DEERE COMMERCIAL WORKSITE PRODUCTS
SKID STEERS**

270 SKID STEER

Continued

CODE	ATTACHMENT DESCRIPTION	WEIGHT	REF	LIST PRICE
IDENTIFIER		LBS.		US \$

WHEELS AND TIRES

Continued

2330	14x17.5 12 PR SKS Extra-Wall <i>NOTE: Gives 76.2 in. Skid Steer width</i>			In Base Price
2320	14x17.5 14 PR Hauler HD <i>NOTE: Gives 76.5 in. Skid Steer width</i>		443K37	444.00
2180	14x17.5 14 PR Galaxy "Beefy Baby II" HD <i>NOTE: Gives 77.1 in. Skid Steer width</i>		565K38	706.00
2185	14x17.5 SuperFlex Foam Filled Galaxy "Beefy Baby II" <i>NOTE: Not Compatible with Tracks</i>		441K553	2,044.00
2200	9x16 Mitco "Duro Cushion" Solid <i>NOTE: Gives 72.7 in. Skid Steer width</i>		248K35	1,099.00
2290	12x16.5 8 PR SKS Standard Duty <i>NOTE: Gives 73.8 in. Skid Steer width</i>		048K01	(1,054.00)
2310	12x16.5 10 PR SKS Extra-Wall <i>NOTE: Gives 73.4 in. Skid Steer width</i>		565K74	(756.00)
2300	12x16.5 10 PR SKS Hauler HD <i>NOTE: Gives 73.5 in. Skid Steer width</i>		564K98	(656.00)
2070	12x16.5 10 PR Galaxy "Beefy Baby II" HD <i>NOTE: Gives 71.3 in. Skid Steer width</i>		564K22	(556.00)
2075	12x16.5 SuperFlex Foam Filled Galaxy "Beefy Baby II" <i>NOTE: Not Compatible with Tracks</i>		446K41	844.00
2100	33/1550x16.5 12 PR Galaxy "Hippo" Flotation <i>NOTE: Gives 76.6 in. Skid Steer width</i>		403K72	490.00

HYDRAULIC OPTIONS

3000	Standard Base Hydraulics			In Base Price
3001	Hydraulic Self-Leveling		603K30	435.00
3002	High Flow Hydraulics <i>NOTE:</i> <i>* Total 34.9 gpm with High Flow</i> <i>* Not for use with Air Conditioning (8115)</i>		001K368	1,800.00
3003	High Flow Hydraulics and Hydraulic Self-Leveling <i>NOTE: Not for use with Air Conditioning (8115)</i>		601K698	2,235.00
3004	Standard Base Hydraulics with Hydraulic Quik-Tatch		005K51	725.00
3005	Hydraulic Self-Leveling with Hydraulic Quik-Tatch		606K81	1,160.00

**KITS AND ACCESSORIES - FACTORY
INSTALLED**

8000	3-Inch Seat Belt		209K1	120.00
------	------------------	--	-------	--------

JOHN DEERE COMMERCIAL WORKSITE PRODUCTS
SKID STEERS

270 SKID STEER

Continued

CODE	ATTACHMENT IDENTIFIER	DESCRIPTION	WEIGHT LBS.	REF.	LIST PRICE US\$
		NOTE: * Required in British Columbia and California/Construction Industry Safety Orders Use of 3 Inch Wide Webbing Seat Belt * Not for use with Shoulder Belt (R150)			
8200		3-Inch Seat Belt with Shoulder Harness NOTE: Not for use with Cab Enclosure (8060) or Demolition Door Kit (8070)		002K09	275.00
8205		3-Inch Seat Belt with Shoulder Harness for Cab & Demo Kits NOTE: Only for use with Cab Enclosure (8060) and Demolition Door Kit (8070)		002K09	275.00
8115		Air Conditioning / Heater / Defroster NOTE: * Recommend Cab Enclosure (8060) and Floor Cover Plates (8080) * Not for use with High Flow (3002, 3003) * Not for use with Heater / Defroster Kit (8110)		241K291	1,699.00
8040		Backup Alarm		321K38	182.00
8050		Black Heater Kit		205K3	70.00
8060		Cab Enclosure NOTE: * Includes Shoulder Belt * Not for use with Demolition Door Kit (8070) * Not for use with Shoulder Belt (8150)		129K78	1,287.00
8070		Demolition Door Kit NOTE: * Includes Shoulder Belt * Not for use with Cab Enclosure (8060) * Not for use with Shoulder Belt (8150)		447K17	944.00 ✓
8075		Dual Flashers		589K9	131.00
8080		Floor Cover Plates		642K9	39.00
8090		Hand Controls		002K85	375.00
8110		Heater / Defroster Kit NOTE: * Recommend Cab Enclosure (8060) and Floor Cover Plates (8080) * Not for use with Air Conditioning / Heater / Defroster (8115)		926K58	867.00
8210		Horn		447K1	94.00
8130		Rear Weights Bracket Kit NOTE: Requires Eight R66949Y Weights		001K33	175.00 ✓
8150		Shoulder Belt NOTE: * Not for use with 3-inch Seat Belt (8000) * Not for use with Cab Enclosure (8060) * Not for use with Demolition Door Kit (8070)		801K17	155.00
8181		Suspension Seat		002K47	325.00

**JOHN DEERE COMMERCIAL WORKSITE PRODUCTS
SKID STEERS**

270 SKID STEER

Continued

CODE	ATTACHMENT IDENTIFIER	DESCRIPTION	WEIGHT LBS.	REF.	LIST PRICE US \$
8220		Top Window		804K35	60.00
BUCKETS (Refer to Bucket Compatability Chart)					
<i>See Attachments for Multi-Purpose Buckets</i>					
9040	KV11631	72 in. Construction Bucket (17.8 cu. ft.)		005K49	722.37
9210	KV12041	72 in. Tooth Bucket (17.8 cu. ft.)		006K59	867.11
9320	KV21474	72 in. Utility Bucket (22.6 cu. ft.)		005K95	782.89
9160	KV11642	72 in. Manure / Slurry Bucket (17.8 cu. ft.)		205K09	670.00
9110	KV11637	72 in. Foundry Bucket (16.0 cu. ft.)		205K47	720.00
9051	KV22751	78 in. HD Construction Bucket (19.4 cu. ft.)		006K36	836.84
9221	KV22755	78 in. HD Tooth Bucket (19.4 cu. ft.)		007K59	998.68
9330	KV22802	78 in. HD Utility Bucket (24.5 cu. ft.)		006K35	835.52
9120	KV22758	78 in. HD Foundry Bucket (17.8 cu. ft.)		005K92	778.95
9061	KV22752	84 in. HD Construction Bucket (21.0 cu. ft.)		007K19	946.05
9231	KV22756	84 in. HD Tooth Bucket (21.0 cu. ft.)		008K13	1,069.74
9171	KV11643	84 in. Manure / Slurry Bucket (22.5 cu. ft.)		205K85	770.00
9340	KV21470	84 in. HD Utility Bucket (27.0 cu. ft.)		006K75	888.16
EXPORT CODES					
9260	KV23803	French Canadian Operator's Manual and Decals			No Charge
9240	KV23801	Spanish Operator's Manual and Decals			No Charge
KITS AND ACCESSORIES - FIELD INSTALLED					
WHEELS AND TIRES (FOUR):					
KV21887		14x17.5 12 PR SKS Extra-Wall		561K486	1,956.00
KV21892		14x17.5 14 PR Hauler HD		001K824	2,400.00
KV14691		14x17.5 14 PR Galaxy "Beefy Baby II" HD		122K023	2,662.00
KV20710		14x17.5 SuperFlex Foam Filled Galaxy "Beefy Baby II"		003K040	4,000.00
KV14687		9x16 Milco "Duro Cushion" Solid		002K356	3,100.00

1 March 2003 US

S-10-2450T- 4

**JOHN DEERE COMMERCIAL WORKSITE PRODUCTS
EQUIPMENT FOR SKID STEERS**

**WORKSITE PRO BP84 PICK-UP BROOM
Equipment for Base Machine**

Specifications:

10-28 gpm Hydraulic Flow
50/50 Poly Wire Brush
25 in. Diameter Brush

2 Center Wheels for
Better Stability
Baffle to Material in
Bucket
Infinite Brush Height

84 in. Sweeping Width
98 in. Overall Width
100 in. Sweeping Width with
Gutter Brush
16.7 Cubic Feet Hopper
Capacity

Standard Equipment:

Specifications:

CODE IDENTIFIER	ATTACHMENT DESCRIPTION	WEIGHT LBS.	REF.	LIST PRICE US \$
-----------------	------------------------	-------------	------	------------------

Select One Code From Each Required Category

BASE CODE

F.O.B. Dubuque, Iowa

0311KV	WORKSITE PRO BP84 PICK-UP BROOM (For 240-280 SS)		244K103	5,399.00 ✓
--------	---	--	---------	------------

ATTACHMENTS FOR FIELD CONVERSION

KV23660	Single Gutter Brush		648K85	1,139.00
KV23681	Second Gutter Brush <i>NOTE: Must also order Single Gutter Brush to complete</i>		605K39	710.00

**JOHN DEERE COMMERCIAL WORKSITE PRODUCTS
EQUIPMENT FOR SKID STEERS**

WORKSITE PRO MP78 MULTI-PURPOSE BUCKET
Equipment for Base Machine

Performance:

- Low Profile Design for Superior Visibility
- Wear Resistant 1055 H.C. Steel at Key Wear Points
- 3/4 x 6 in. at Cutting Edge
- 1/2 x 3 in. at Dozer Edge
- 3/4 x 4 in. at Clam Back Edge
- 3/8 x 3 in. at End Plates
- 3 1/2 x 4 in. Bottom Plate Runners
- Notched Jaws on Clam For Grappling

- Superior Designed Strength: Triangular Box Section Structure at Rear Dozer Blade
- Reinforced Bucket Sides

(0.28 cu. m)

- Dual Hydraulic Cylinders: 6 in. Stroke
- 2.75 in. Bore
- 1.5 in. Rod Diameter

- Durability Convertability: Predrilled Cutting Edge for Optional "Bolt-On" Reversible Cutting Edge
- Predrilled Sides for Optional "Bolt-On" Tooth Bar

- Quik-Tatch Mounting with 1/2 in. Couplers and Hoses

NOTE: Rear Ballast is Not Required. However, Depending on Material Density Being Handled, Rear Ballast May Enhance Machine's Stability.

- Capacities: Heaped 14.1 cu. ft. (0.40 cu. m)
- Struck 10.0 cu. ft.

CODE	ATTACHMENT IDENTIFIER	DESCRIPTION	WEIGHT LBS	REF.	LIST PRICE US\$
------	-----------------------	-------------	------------	------	-----------------

Select One Code From Each Required Category

BASE MACHINE

F.O.B. Dubuque, Iowa

0203KV		WORKSITE PRO MP78 MULTI-PURPOSE BUCKET (For 240-280 SS)		241K975	2,599.00
--------	--	--	--	---------	----------

ATTACHMENTS FOR FIELD CONVERSION

KV14520		Rear Weight Bracket Kit (240, 250) NOTE: Requires Eight R66949Y Weights		001K14	150.00
KV16627		Rear Weight Bracket Kit (280, 270, & 280) NOTE: Requires Eight R66949Y Weights		001K14	150.00
X8	R66949Y	Yellow 44 lb. Quik-Tatch Weight		252K6	35.00
KV12296		78 in. Tooth Bar - 8 Teeth		272K91	383.25
KV12758		78 in. Bolt-On Cutting Edge NOTE: Requires Eight Grade 8 Plow Bolts and Nuts			See Parts
PB750225		Box of #3 Grade 8 Plow Bolts and Nuts NOTE: Quantity of 70 Bolts and Nuts Per Box			See Parts

**JOHN DEERE COMMERCIAL WORKSITE PRODUCTS
EQUIPMENT FOR SKID STEERS**

WORKSITE PRO 48 IN. PIN PALLET FORK
Equipment for Base Machine

Forks "Float" with Contour
of Ground
Features Unlimited Number of
Tine Positions

Robust, Single Piece
Backrest
Unrestricted Visibility to
Fork Tips

NOTE: Rear Ballast is Not
Required But May Enhance
Machine Stability.

CODE	ATTACHMENT DESCRIPTION	WEIGHT	REF.	LIST PRICE
IDENTIFIER		LBS.		US\$

Select One Code From Each Required Category

BASE MACHINE

F.O.B. Dubuque, Iowa

0256KV	WORKSITE PRO 48 IN. PIN PALLET FORK (For 240-280 SS)		806K49	855.00
--------	---	--	--------	--------

ATTACHMENTS FOR FIELD CONVERSION

KV14620	Rear Weight Bracket Kit (240, 250) <i>NOTE: Requires Eight R66949Y Weights</i>		001K14	150.00
KV16627	Rear Weight Bracket Kit (260, 270, & 280) <i>NOTE: Requires Eight R66949Y Weights</i>		001K14	150.00
R66949Y	Yellow 44 lb. Quik-Tatch Weight		252K6	35.00
KV19147	Pin Fork Mounting Frame and Guard		003K03	398.68

**JOHN DEERE COMMERCIAL WORKSITE PRODUCTS
EQUIPMENT FOR SKID STEERS**

WORKSITE PRO 14 IN. STEEL TRACKS
Equipment for Base Machine

Self Cleaning CatTrac Design
Replaceable Bushings, Links,
and Pads
Easy-To-Use Track Mounting
Binder

Heavy Duty Bushings for Long
Wear Life

Drilled Link Holes for
Increased Strength
Outside Plate is Open for
Easy Cleaning and Length

Adjustment

NOTE: Tires must be in Wide
Position when Tracks are
Installed. Wheel Spacers
are NOT Required on 260-270.

CODE IDENTIFIER	ATTACHMENT DESCRIPTION	WEIGHT LBS.	REF.	LIST PRICE US\$
-----------------	------------------------	-------------	------	-----------------

Select One Code From Each Required Category

BASE MACHINE

F.O.B. Dubuque, Iowa

0026KV	WORKSITE PRO 14 IN. STEEL TRACKS <i>(For 260-280 SS with 14 in. Heavy Duty Tires)</i>		882K308	3,038.00
--------	--	--	---------	----------

KITS

1000	Track Guard Assembly Kit for 260 and 270 with 14 in. Heavy Duty Tires		364K6	61.00
------	---	--	-------	-------

1001	Axle Block Kit for 280		364K6	61.00
------	------------------------	--	-------	-------

ATTACHMENTS FOR FIELD CONVERSION

KV17333	Track Guard Assembly Kit for 260 and 270 with 14 in. Heavy Duty Tires		364K6	61.00
KV23789	Axle Blocks for 280		364K6	61.00
KV22838	Binder			See Parts
KV22839	Strap			See Parts

PRICE: \$437.00

- (2) 4001. High efficiency bypass oil purification system. This system is designed to reduce or eliminate hydraulic oil changes and extend its useful life. The Puradyn Oil Filtration System or approved equivalent. Puradyn Filter Technologies, Inc. 1-800-488-0577.

PRICE: \$437.00

- (3) 4002. Automatic lubrication system. System shall consist of an electronically operated pump delivering fluid grease of NLGI grades 000 and 00 to adjustable piston distributors that can meter the amount of grease to each lubrication point. Vogel Automatic Lubrication System of approved equivalent. Vogel Lubrication, Inc. (757) 380-8585, email: vogel@vogel-lube.com.

PRICE: \$3,694.00

- (4) 8001. Special state color, DOT Yellow, Federal Yellow No. 13538, DuPont #L9069A, ACME No. 2712, Deere No. PT102, or approved equivalent, (may be Contractor painted if factory painting is not available). NOTE: The entire unit, including Options, shall be painted the same color.

PRICE: \$2,465.00

- (5) 9901. Transport trailer, designed specifically to transport a skid loader of the model Bid. Trailer Bid must have two (2) axles with two (2) leaf spring suspension and hydraulic brakes on all four wheels. Include a 2-inch ball surge coupler, safety chains, full fenders, and folding loading ramps.

PRICE: \$4,717.89

760-460-100

MAKE JOHN DEERE

CONTRACTOR	MODEL	*DISCOUNT F.O.B. CONTRACTOR	PRICE
J D CONSTRUCTION & FORESTRY EQUIP	270	28%	\$23,714.96 (16)

- 1. Percentage discount off Manufacturer's current published retail prices for non-specified Options for a State of Florida Base Unit and any Optional models bid. (The percentage discount is applied to the Manufacturer's current published retail prices.)

28% Discount

**Date of current published retail price book: 05/03/02

*Discount for pickup by ordering agency at Contractor's place of business.

**NOTE: ALL DATES MUST BE FOR THE CURRENT PUBLISHED RETAIL PRICE BOOK.



Municipal Agency: Lee County Utilities Dept.
John Deere 230CLC Excavator, 169 Net HP, 54,000 lb. operating weight
Commodity Code #760-840-400
Florida State Term Contract Number 760-001-03-1
Expires: May 31, 2004

A. Base Unit	per State Contract Specifications: (JD 230CLC)	\$132,425.31
Includes:	32" Track Pads	One Piece Boom
	Standard Medium Arm	42" 1.75 yd. Heavy Duty Bucket
	Side Cutters	ROPS Cab w/ Air Conditioning
	Fire Extinguisher	AM-FM Radio
	6 Month Standard Warranty	One operator & parts manual
B. Options Priced On Contract: (Net Prices)		None
C. Options @ 44% off Current Manufacturer's List Price: (Net Prices)		
	1. Additional 36" Severe Duty Plate Lip bucket	\$ 3,199.28
	2. Side Cutter Kit for 36" bucket	\$ 344.40
	3. Set of four Tiger style teeth for 36" bucket (TT400)	\$ 556.80
D. Additional Dealer Installed Non-Contract Options: (Net Prices)		
	1. 100 hour Break-In Service	\$ 500.00
	2. SECURE 5 Year / 5,000 hour Full Machine Warranty	\$ 9,098.00
	3. Thumb Attachment, Mechanical Pin-on for 42" bucket	\$ 5,724.00
	4. SMART 3,000 hour Preventative Maintenance Contract	\$ 8,981.00
	5. 2 sets of Operator, Parts and Service Manuals & 3 keys	\$ 250.00
	Subtotal for additional options: (B, C & D)	\$ 28,653.48
	Total Price including all options:	\$161,078.79
	• FOB Lee County, FL Fleet Management Division	
	• Allow 90 Days for delivery	

Direct Purchase Orders To:
Eny Sanchez, Governmental Sales
Nortrax Equipment Co. SE LLC
 4343 N.W. 76th Avenue
 Phone (305) 592-5740 X-224 Fax: (305) 513-4353 Cell: (305) 586-2921

(Subject To Change Without Notice)

CONSTRUCTION PRODUCTS**C-3-230C LC-1****230C LC EXCAVATOR****Equipment for Base Machine****ENGINE:**

John Deere PowerTech 6068H -
6.8L (414 Cu. In.)
Meets EPA Off-Road Emissions
Certification
169 SAE Net HP
Turbocharger
Charge Air Cooler
Auxiliary Drive Pad
Antifreeze Protection to -14
Degrees F (-17 Degrees C)
Dual Dry-Type Air Filter with
Restriction Indicator
Electronic Engine Control Unit
(ECU) with Diagnostics
Capability
Low Noise Fan with Guard
Full Flow Oil Filter
Heavy Duty, Low Maintenance
Batteries (180 Minute
Reserve)
Fuel Filter
Isolated Mounted
Radiator / Oil Cooler Trash
Screen
Underhood Muffler with
Vertical Exhaust
45 Amp Alternator - 24 Volt
Automatic Belt Tension Device
Water Separator

HYDRAULICS:

Open Center, Load Sensing with
Variable Displacement Pumps
Hydraulic Pilot Controls
Axial Piston Swing Motor
Multiple Wet Disk Swing Brake
Auxiliary Valve Section
Boom and Arm Reduced-Drift
Valves
Auto Power Lift
Hydraulic Tank Sight Gauge

UNDERCARRIAGE:

32 In. (800 mm) Track Pads
Front and Center Track Guides
Planetary Final Drive
Two Speed Propel with
Auto-Shift
Axial Piston Propel Motors
X-Frame Car body
Hydraulic Track Adjuster
Sealed Track Chain
Reinforced Front Idler Support

UPPER STRUCTURE:

Right and Left Mirrors
Toolbox
Vandal Locks for:
Cab Door
Service Doors
Fuel Cap
Toolbox
Hydraulic Reservoir
Counterweight, 11,265 Lbs.
(5,110 Kg.)
Work Lights:
One Mounted on Frame
One Mounted on Boom

FRONT ATTACHMENTS:

Less Boom
Less Arm
Less Bucket

OPERATOR'S STATION:

Adjustable Control Positions
(Levers, to Seat, to Pedals)
AM-FM Radio
Auto Idle Mode
Auto Acceleration Mode
Mode Selection:
Three Power Modes
Two Work Modes
Auto Climate Control - Air
Conditioner, Heater with

Pressurizer

Horn
Hourmeter
Interior Light
12V-60W, 5 Amp, Call
Phone-Power Outlet
Monitor System with:
Diagnostics Capability
Auto Idle/Auto Acceleration
Indicator
Alternator Charge Indicator
Engine Coolant Temperature
Warning Indicator with
Audible Alarm
Engine Oil Pressure Warning
Indicator with Audible Alarm
Low Fuel Indicator
Work-Lights-On Indicator
Engine Coolant Gauge
Engine Check Indicator
Fuel Gauge
Wiper Mode Indicator
Work Mode Indicator
Windshield Wiper/Washer with
Constant or Intermittent
Speed
Transparent Tinted Roof Hatch
with Sun Shade
Motion Alarm with Cancel
Switch
Coat Hook
Deluxe Adjustable Seat with
Suspension and Reclining
Backrest
with (4 in., 100mm)
Adjustable Lumbar, Armrest
and Headrest
2 In. Retractable Seat Belt
Hot/Cold Box Compartment
Large Cup Holder
Tinted Safety Glass
Floor Mat

CODE

DESCRIPTION

LIST PRICE
US\$

Select One Code From Each Required Category

BASE MACHINE	
1330FF	230C LC EXCAVATOR

183,173.00

7 January 2002
US

(Subject To Change Without Notice)

CONSTRUCTION PRODUCTS

C-3-230C LC-2

230C LC EXCAVATOR
Continued

CODE	DESCRIPTION	LIST PRICE US \$
TRACK SHOES		
3275	24 in. (600 mm) Triple Semi Grouser Shoes NOTE: * Recommended for rock terrain, hard ground and stumps.	(1,414.00)
3300	28 in. (700 mm) Triple Semi Grouser Shoes NOTE: * Recommended for general conditions and soft terrain.	(1,035.00)
3350	32 in. (800 mm) Triple Semi Grouser Shoes NOTE: * Recommended for extremely soft terrain.	In Base Price
BOOM		
6801	Less Boom, Arm Cylinder, Boom Cylinders and Plumbing on Boom (Pin Connecting Boom to Mainframe and the Two Boom Cylinder Pins are Included in Upperstructure) NOTE: * Requires Code 7001, Less Arm. * Recommend AT189840 Hydraulic Filter Restriction Indicator.	In Base Price
6835	19 Ft. 6 in. (6.0 M.) One Piece Boom, Arm Cylinder and Plumbing	22,767.00
ARMS		
7001	Less Arm, Bucket Cylinder, Bucket Linkage and All Attaching Pins and Hoses NOTE: * Recommend AT189840, Hydraulic Filter Restriction Indicator.	In Base Price
7180	9 Ft. 9 in. (2.96 M) Arm with Bucket Cylinder and Linkage	11,366.00
7180	11 Ft. 10 in. (3.61 M) Arm with Bucket Cylinder and Linkage	13,359.00
BUCKETS		
8001	Less Bucket	In Base Price
8320	36 in. (900MM) 1.16 Cu. Yd. Heavy Duty Bucket with Four (4) Hensley Style Fanggs (TF400)	6,299.00
8330	42 in. (1067MM) 1.35 Cu. Yd. Heavy Duty Bucket with Five (5) Hensley Style Fanggs (TF400)	6,911.00
8340	48 in. (1200MM) 1.60 Cu. Yd. Heavy Duty Bucket with Six (6) Hensley Style Fanggs (TF400)	7,404.00
8350	54 in. (1373MM) 1.82 Cu. Yd. Heavy Duty Bucket with Six (6) Hensley Style Fanggs (TF400)	7,851.00

7 January 2002
US

(Subject To Change Without Notice)

CONSTRUCTION PRODUCTS

C-3-230C LC-3

230C LC EXCAVATOR
Continued

CODE	DESCRIPTION	LIST PRICE US \$
BUCKETS		
Continued		
8420	36 In. (900MM) 1.48 Cu. Yd. Heavy Duty High Capacity Bucket with Four (4) Hensley Style Fangs (TF400)	6,017.00
8430	42 In. (1067MM) 1.75 Cu. Yd. Heavy Duty High Capacity Bucket with Five (5) Hensley Style Fangs (TF400)	6,372.00
8440	48 In. (1200MM) 2.03 Cu. Yd. Heavy Duty High Capacity Bucket with Six (6) Hensley Style Fangs (TF400)	7,028.00
SPECIAL EQUIPMENT - ORDER AS DESIRED		
9010	Boom Cylinders with Plumbing to Main Frame NOTE: * Requires 6801, Less Boom, and Code 7001, Less Arm.	5,932.00
9040	Auxiliary Hydraulic Lines NOTE: * Does not include controller. See Attachment for Field Conversion for controller options. * Includes stop valves at end of arm and a low pressure return line to tank with a 2-way valve. * Auxiliary function flow rate is 50 GPM and maximum operation pressure is 4000 PSI. * For use with Code 7180, 11 Ft. 10 In. (3.81 M) Arm.	3,923.00
9045	Auxiliary Hydraulic Lines NOTE: * Does not include controller. See Attachment for Field Conversion for controller options. * Includes stop valves at end of arm and a low pressure return line to tank with a 2-way valve. * Auxiliary function flow rate is 50 GPM and maximum operation pressure is 4000 PSI. * For use with Code 7180, 9 Ft. 9 In. (2.96 M) Arm.	3,923.00
9280	French Operator's Manual	No Charge
9280	Spanish Operator's Manual	No Charge
DEALER-INSTALLED ATTACHMENTS		
ARMS:		
AT195090	9 Ft. 9 In. (2.96 m) Arm with Bucket Cylinder, Hoses and Linkage	11,388.00
AT195091	11 Ft. 10 In. (3.8 m) Arm with Bucket Cylinder, Hoses and Linkage	13,359.00
GENERAL PURPOSE BUCKETS		
NOTE: * All Buckets come WITHOUT teeth, side cutters, and pins. * Recommended numbers of teeth are listed with each bucket. * Tooth placement can be varied at no charge. * Horizontal in lieu of Vertical Wear Strips are available at the same price. * All Buckets are F.O.B. Schofield, WI.		
AT167279	24 In. (600 mm), .95 Cu. Yd. 3 Teeth	4,534.00

7 January 2002
US

(Subject To Change Without Notice)

CONSTRUCTION PRODUCTS

C-3-230C LC-4

230C LC EXCAVATOR

Continued

CODE	DESCRIPTION	LIST PRICE US \$
AT183628	30 In. (750 mm), 1.20 Cu. Yd. 4 Teeth	4,988.00
AT183629	36 In. (900 mm), 1.48 Cu. Yd. 5 Teeth	5,178.00
AT183631	42 In. (1067 mm), 1.75 Cu. Yd. 5 Teeth	5,462.00
AT183632	48 In. (1200 mm), 2.03 Cu. Yd. 6 Teeth	5,748.00
HEAVY-DUTY BUCKETS		
<i>NOTE:</i>		
* All Buckets come <i>WITHOUT</i> teeth, side cutters, and pins.		
* Recommended numbers of teeth are listed with each bucket.		
* Tooth placement can be varied at no charge.		
* Horizontal in lieu of Vertical Wear Strips are available at the same price.		
* All Buckets are F.O.B. Schofield, WI.		
AT172478	30 In. (750 mm), .85 Cu. Yd. 4 Teeth	5,145.00
AT172477	36 In. (900 mm), 1.18 Cu. Yd. 4 Teeth	5,500.00
AT172478	42 In. (1067 mm), 1.38 Cu. Yd. 5 Teeth	5,912.00
AT172479	48 In. (1200 mm), 1.60 Cu. Yd. 6 Teeth	6,208.00
AT172480	54 In. (1373 mm), 1.82 Cu. Yd. 8 Teeth	6,653.00
HEAVY-DUTY HIGH CAPACITY BUCKETS		
<i>NOTE:</i>		
* All Buckets come <i>WITHOUT</i> teeth, side cutters, and pins.		
* Recommended numbers of teeth are listed with each bucket.		
* Tooth placement can be varied at no charge.		
* Horizontal in lieu of Vertical Wear Strips are available at the same price.		
* All Buckets are F.O.B. Schofield, WI.		
AT183638	24 In. (600 mm), .92 Cu. Yd. 3 Teeth	4,598.00
AT183639	30 In. (750 mm), 1.20 Cu. Yd. 4 Teeth	4,881.00
AT183640	36 In. (900 mm), 1.48 Cu. Yd. 4 Teeth	5,218.00
AT183641	42 In. (1067 mm), 1.75 Cu. Yd. 5 Teeth	5,373.00
AT183645	48 In. (1200 mm), 2.03 Cu. Yd. 6 Teeth	5,800.00
SEVERE-DUTY CAST LIP BUCKETS		
<i>NOTE:</i>		
* All Buckets come <i>WITHOUT</i> teeth, side cutters, and pins.		
* Recommended numbers of teeth are listed with each bucket.		
* Tooth placement can be varied at no charge.		
* Horizontal in lieu of Vertical Wear Strips are available at the same price.		
* All Buckets are F.O.B. Schofield, WI.		
AT171743	36 In. (900 mm), 1.18 Cu. Yd. 4 Teeth	7,813.00
AT171745	42 In. (1067 mm), 1.38 Cu. Yd. 5 Teeth	8,209.00
SEVERE-DUTY PLATE LIP BUCKETS		

7 January 2002
US

(Subject To Change Without Notice)

CONSTRUCTION PRODUCTS

C-3-230C LC-5

230C LC EXCAVATOR
Continued

CODE	DESCRIPTION	LIST PRICE US \$
------	-------------	---------------------

NOTE:
 * All Buckets come WITHOUT teeth, side cutters, and pins.
 * Recommended numbers of teeth are listed with each bucket.
 * Tooth placement can be varied at no charge.
 * Horizontal in lieu of Vertical Wear Straps are available at the same price.
 * All Buckets are F.O.B. Schofield, WI.

OPTION #1

AT163645	30 in. (750 mm), .95 Cu. Yd. 4 Teeth	5,344.00
AT163646	36 in. (900 mm), 1.16 Cu. Yd. 4 Teeth	5,713.00
AT163647	42 in. (1067 mm), 1.38 Cu. Yd. 5 Teeth	5,828.00

DITCHING BUCKETS:
 (No Teeth Required):
 NOTE: No Teeth Required.

AT160745	60 in. (1500 mm), 1.34 Cu. Yd. NOTE: Not for use on long-front booms.	5,100.00
----------	--	----------

AT160746	72 in. (1800 mm), 1.86 Cu. Yd. NOTE: Not for use on long-front booms.	5,404.00
----------	--	----------

AT160685	60 in. (1500 mm), .75 Cu. Yd.	3,208.00
----------	-------------------------------	----------

ROAD-BUILDER KITS for Heavy Duty Buckets:
 NOTE: The kit includes T1 moldboard, horizontal wear bars and extra side wear plates installed.

AT167255	Road-Builder Kit for 30 in. Bucket NOTE: Requires 30 in. Heavy-Duty Bucket.	936.00
----------	--	--------

AT167256	Road-Builder Kit for 36 in. Bucket NOTE: Requires 36 in. Heavy-Duty Bucket.	936.00
----------	--	--------

AT167257	Road-Builder Kit for 42 in. Bucket NOTE: Requires 42 in. Heavy-Duty Bucket.	936.00
----------	--	--------

AT167258	Road-Builder Kit for 48 in. Bucket NOTE: Requires 48 in. Heavy-Duty Bucket.	936.00
----------	--	--------

AT167259	Road-Builder Kit for 54 in. Bucket NOTE: Requires 54 in. Heavy-Duty Bucket.	936.00
----------	--	--------

ROAD-BUILDER KITS for Heavy-Duty High-Capacity Buckets
 NOTE: The kit includes T1 moldboard, horizontal wear bars and extra side wear plates installed.

AT167260	Road-Builder Kit for 24 in. Bucket NOTE: Requires 24 in. Heavy-Duty, High-Capacity Bucket.	936.00
----------	---	--------

AT167261	Road-Builder Kit for 30 in. Bucket NOTE: Requires 30 in. Heavy-Duty, High-Capacity Bucket.	936.00
----------	---	--------

AT167262	Road-Builder Kit for 36 in. Bucket NOTE: Requires 36 in. Heavy-Duty, High-Capacity Bucket.	936.00
----------	---	--------

AT167263	Road-Builder Kit for 42 in. Bucket NOTE: Requires 42 in. Heavy-Duty, High-Capacity Bucket.	936.00
----------	---	--------

SIDE CUTTERS FOR BUCKETS

(Subject To Change Without Notice)


CONSTRUCTION PRODUCTS

C-3-230C LC-6

230C LC EXCAVATOR
Continued

CODE	DESCRIPTION	LIST PRICE US \$
AT131080	Side Cutter Kit NOTE: * For use with general purpose buckets. * Includes 2 side cutters and attaching hardware.	815.00
AT131085	Side Cutter Kit NOTE: * For use with heavy-duty high capacity, severe-duty cast lip and plate lip buckets only. * Includes 2 side cutters and attaching hardware.	815.00
AT167878	KIL Edge Protector NOTE: * Protects bucket side cutting edges. Does not extend width of bucket. * Includes 2 protectors and attaching hardware. * For use with heavy-duty and heavy-duty high capacity buckets. TOOTH KITS for General Purpose Buckets NOTE: The following includes One Tooth, One Pin and One Adapter installed. Order quantity desired.	530.00
AT178530	(1) Fanggs (TF330)—Hensley Style	187.11
AT178532	(1) Standard (TX330)—Hensley Style	184.94
AT178534	(1) Tiger (TT330)—Hensley Style	187.16
AT178538	(1) Twin Tiger (TX330WT)—Hensley Style	197.84
AT188374	(1) Standard (Super-V EV33SYL)	178.81
AT183544	(1) Standard (EX27SYL)—Vertalok Style	167.23
AT183545	(1) Tiger (EX27VIP)—Vertalok Style	154.22
AT183546	(1) Flare (EX27S8F)—Vertalok Style	195.48
AT183547	(1) Twin Tiger (EX27TVIP)—Vertalok Style	188.88
AT187182	(1) Fanggs (CAT TF1U3352D)—Cat Style	128.90
AT187183	(1) Standard (CAT T1U3352)—Cat Style	120.10
AT187194	(1) Tiger (CAT TT1U3352)—Cat Style	121.15
AT187195	(1) Twin Tiger (CAT TX1U3352WT)—Cat Style	127.40
	TOOTH KITS for Heavy-Duty, Heavy-Duty High Capacity, and Severe-Duty Plate Lip Buckets NOTE: The following includes One Tooth, One Pin and One Adapter installed. Order quantity desired.	
AT183548	(1) Fanggs (Hensley - TF400)	247.88
AT183549	(1) Standard (Hensley - TX400)	243.51
AT183550	(1) Tiger (Hensley - TT400)	248.57
AT183551	(1) Abrasion Panel (Hensley - TX400AP)	288.97
AT183552	(1) Flare (Hensley—TX400F)	258.37

OPTION #2



4 REQUIRED

OPTION #3

(Subject To Change Without Notice)

CONSTRUCTION PRODUCTS

C-3-230C LC-7

230C LC EXCAVATOR

Continued

CODE	DESCRIPTION	LIST PRICE U.
AT183553	(1) Twin Tiger (Hensley - TX400WT)	270.30
AT183561	(1) Standard (Super-V EV39SYL)	253.87
AT183554	(1) Standard (Vertalok - EX37SYL)	328.82
AT183555	(1) Tiger (Vertalok - EX37VIP)	318.80
AT183556	(1) Flare (Vertalok - EX37S7F)	367.80
AT183557	(1) Twin Tiger (Vertalok - EX37TVIP)	337.21
AT187198	(1) Fanggs (CAT - TF9W8452D)	238.05
AT187197	(1) Standard (CAT - T9W8452)	230.97
	TOOTH KITS for Severe-Duty Cast Lip Buckets	
	<i>NOTE: The following includes One Tooth, One Pin and One Adapter installed. Order quantity desired.</i>	
AT183825	(1) Fanggs (Hensley - TF400)	199.70
AT183826	(1) Standard (Hensley - TX400)	201.90
AT183827	(1) Tiger (Hensley - TT400)	204.30
AT183828	(1) Abrasion Panel (Hensley - TX400AP)	225.80
AT183832	(1) Twin Tiger (Hensley - TX400WT)	228
	TOOTH KITS for Severe-Duty Plate Lip Buckets	
	<i>NOTE: The following includes One Tooth, One Pin and One Adapter installed. Order quantity desired.</i>	
AT183548	(1) Fanggs (Hensley - TF400)	247.88
AT183549	(1) Standard (Hensley - TX400)	243.51
AT183550	(1) Tiger (Hensley - TT400)	248.57
AT183553	(1) Twin Tiger (Hensley - TX400WT)	270.30
AT183551	(1) Abrasion Panel (Hensley - TX400AP)	268.97
AT180375	(1) Standard (Super-V EV39SYL)	381.81
AT183554	(1) Standard (Vertalok - EX37SYL)	328.82
AT183555	(1) Tiger (Vertalok - EX37VIP)	318.80
AT183557	(1) Twin Tiger (Vertalok - EX37TVIP)	337.21
AT187198	(1) Fanggs (CAT - TF9W8452D)	238.05
AT187197	(1) Standard (CAT - T9W8452)	230.97
	CAB & ELECTRICAL	
AP38783	Cab Window Vandal Protection Kit	1,384.00

7 January 2002
US

Government Sales
4343 N.W. 76th Avenue
Miami, FL 33186
Office: (305) 592-5740 X-224
Fax: (305) 513-4353
Cell: (305) 586-2921



Fax

To: Chevone Peterson **From:** Eny Sanchez

Fax: 239-689-7390 **Pages:** 9

Phone: **Date:** 7/23/2003

Re: Deere 230CLC Price Pages / Quote **CC:**

- Urgent
 For Review
 Please Confirm
 Please Reply
 Please File

• **Comments:**

Chevone,

Fax #4 JD 230CLC Excavator info:

Circled items refer to those options listed in section C on our quotation. 44% Discount applies.

Regards,

Eny

PS More faxes on the way.....

Construction/Industrial Equipment and Forklifts 760-001-03-1

Effective: 10/30/2002 through 5/31/2004

Certification
Legal Information
Exhibit A - General Specifications
Exhibit B - Price Sheets
Ordering Instructions
Sample Purchase Order
Revisions
Complete Contract

760-840-400

MAKE JOHN DEERE

CONTRACTOR	MODEL	*DISCOUNT F.O.B. CONTRACTOR	PRICE
<u>NORTRAX EQUIPMENT</u>	<u>230-LC</u>	<u>\$260.00</u>	<u>\$132,425.31 (19)</u>

1. Percentage discount off Manufacturer's current published retail prices for non-specified Options for a State of Florida Base Unit and any Optional models bid. (The percentage discount is applied to the Manufacturer's current published retail prices.)

44% Discount**Date of current published retail price book: 01/07/02

*Discount for pickup by ordering agency at Contractor's place of business.

**NOTE: ALL DATES MUST BE FOR THE CURRENT PUBLISHED RETAIL PRICE BOOK.Approximate delivery time required after receipt of order: 45-60 DAYS

OPTION CODING: 760-840-401-Option Number, Hydraulic Excavator, Hoe Type, Crawler Mtd.

OPTIONS:

- (1) 1201. High efficiency bypass oil purification system. This system is designed to reduce or eliminate engine oil changes and extend its useful life. The Puradyn Oil Filtration System or approved equivalent. Puradyn Filter Technologies, Inc. 1-800-488-0577.

PRICE: \$820.30

- (2) 4001. Air conditioner for operator compartment.

PRICE: INC

- (3) 4002. High efficiency bypass oil purification system. This system is designed to reduce or eliminate hydraulic oil changes and extend its useful life. The Puradyn Oil Filtration System or approved equivalent. Puradyn Filter Technologies, Inc. 1-800-488-0577.

PRICE: \$951.55

- (4) 4402. Automatic lubrication system. System shall consist of an electronically operated pump delivering fluid grease of NLGI grades 000 and 00 to adjustable piston distributors that can meter the amount of grease to each lubrication point. Vogel Automatic Lubrication System of approved equivalent. Vogel Lubrication, Inc. (757) 380-8585, email: vogel@vogel-lube.com.

PRICE: \$6,660.00



**Quotation for Lee County Utilities Department
John Deere 710G Backhoe Loader, 116 Net HP
Commodity Code #760-960-110
Florida State Term Contract Number 760-001-03-1
Expires: May 31, 2004**

A. Base Unit Price per State Contract Specifications: (310G)		\$ 32,939.89
Includes:	Open ROPS Canopy Mechanical Suspension Seat	
	Two Wheel Drive 19.5LX24 Rear Tires	
	11L-16 Front Tires Standard Hydraulics	
	Standard Backhoe Stick Fire Extinguisher	
	24" Standard Duty Bucket 1.25 Yard GP Loader Bucket	
	Front Bumper Master Battery Disconnect Switch	
B. Popular Options Priced On Contract: (Net Prices)		
3001	Mechanical Front Wheel Drive for 710G (9903)	\$ 6,900.00
9903	Upgrade to 710G Model	\$ 40,334.91
C. Options @ 50% off Current Manufacturer's List Price:		
1.	Upgrade Tires to 21LX28 Rear, 15/19.5 Front (4X4 Only)	\$ 387.00
2.	Extendible Dipperstick Backhoe w/ 5 th Function Valve	\$ 4,144.00
3.	Add 24" Severe Duty Backhoe Bucket	\$ 1,505.00
4.	Deduct 24" Standard Duty Backhoe Bucket (From 310G)	- (\$ 482.50)
5.	Add 3 rd Function Loader Valve for MP or Grapple Bucket	\$ 788.50
6.	Deduct 1.25 Yard Standard Loader Bucket (From 310G)	- (\$ 1,000.00)
7.	1630 lbs. Front Counterweight	\$ 643.50
8.	Deluxe Lighting Package	\$ 142.50
9.	95 Amp Alternator (ROPS units only)	\$ 31.00
D. Additional Dealer Installed Non-Contract Options:		
A.	100 Hour Break-In Service	\$ 600.00
B.	SECURE 5 Year/5000 Hour Full Machine Warranty	\$ 11,479.00
C.	JRB Hydraulic Quick Coupler for Loader	\$ 3,575.00
D.	JRB 1.5 Yard Clamshell 4in1 Bucket with Edge for Coupler	\$ 8,675.00
E.	JRB Jumper Hose Kit for Bucket, Installed	\$ 600.00
F.	JRB Construction Forks for Coupler, 60" x 48"	\$ 4,545.00
G.	SMART 3,000 hours Preventative Maintenance Contract	\$ 8,277.00
H.	2 Sets of Operator, Parts and service manuals & 3 Keys	\$ 250.00
	Subtotal for all additional options (B, C, & D):	\$ 91,394.91
Total Price including all options:		\$124,334.80
FOB Lee County, FL Fleet Management Division		
Allow 60 days for delivery		

Direct Purchase Orders To:

Eny Sanchez, Governmental Sales

Nortrax Equipment Co. SE LLC

4343 N.W. 76th Avenue, Miami, FL 33166

Ph: (305) 592-5740 X-224 Fax: (305) 513-4353 Cell: (305) 586-2921

Government Sales
4343 N.W. 76th Avenue
Miami, FL 33166
Office: (305) 592-5740 X-224
Fax: (305) 513-4353
Cell: (305) 586-2921



Fax

To: Chevone Peterson **From:** Eny Sanchez

Fax: 239-689-7390 **Pages:** 9

Phone: **Date:** 7/23/2003

Re: Deere 230CLC Price Pages / Quote **CC:**

- Urgent
 For Review
 Please Confirm
 Please Reply
 Please File

● **Comments:**


Chevone,

Fax #5 JD 710G Backhoe info:

Circled items refer to those options listed in section C on our quotation. 50% Discount applies.

Note: As I went back and checked my own pricing, I noticed that a few of the options prices have actually gone down since my last quote so I am revising my price which will reduce the overall cost by \$700.00 to \$124,334.80.

Regards,



Eny

PS: Last fax package. Call me if you have any questions.

(Subject To Change Without Notice)

UTILITY PRODUCTS

710G BACKHOE LOADER

Equipment for Base Machine

ENGINE:

John Deere PowerTech 606BT
6.8L (414 Cu. In.)
Rated hp: 129 SAE Gross hp /
118 SAE Net hp
Meets EPA Tier II Off-Road
Emission Certification
Turbocharged, Isolation
Mounted
Engine Coolant -34 Degrees F.
(-37 C)
Sucker-Type Cooling Fan
Spin-On Engine Oil Filter
Quick Release John Deere Fuel
Filter with Water Separator
Oil-to-Water Engine Oil Cooler
Dual Safety Element Dry-Type
Air Cleaner with Precooler,
Aspirator and Restriction
Monitor on Console
Muffler, Underhood, with
Vertical Curved Exhaust Stack
Turbocharger Provides Spark
Arresting
Pre-Wired for Ether Starting
Aid
Enclosed Safety Fan Guard
POWERTRAIN:
Engine Mounted Powershift
Transmission and Reverse
with Torque Converter
Isolation Mounted to
Mainframe
Electric Clutch Cut Off on
Gear Shift and Loader Lever
Planetary Final Drives
Differential Lock - Electric
Foot Switch Controlled
Non-Powered Front Axle
Hydrostatic Power Steering
with Emergency Manual Mode
Hydraulic Service Brakes
Inboard, Wet Disc, Self
Adjusting and Self Equalizing
(Conforms to SAE J1473,
ISO3450)
Parking/Emergency Brakes:
Independent of Service Brakes
Spring Applied, Hydraulic
Release with Electric Switch
Control
Oil to Air Cooler
Reverse/Torque Converter
Transaxle and Brakes
BACKHOE:
18 Ft. 2 In. Digging Depth

Enclosed Single Boom Cylinder
Backhoe Transport Lock Lever
Swing Locking Pin Stored in
Operator's Station
Two Lever Backhoe Controls
Reversible Stabilizer Foot
Independent Isolation Mounted
Stabilizer Valve with
Two-Direction Anti-Drift
Valves
Less Bucket with Bucket Pins
LOADER:
Return to Dig Feature
Bucket Level Indicator
Hydraulic Self Leveling
Single Lever Control with
Electric Clutch Cutoff
Less Bucket with Bucket Pins
Loader Boom Service Lock
(Conforms to SAE J38)
OPERATOR STATION:
Modular Design ROPS/FOPS
Canopy Isolation Mounted with
Molded Roof (Conforms to SAE
J1040)
Left and Right Front Access
Slip-Resistant Steps and
Ergonomically Located
Handholds (Conforms to SAE
J185)
Seat, Deluxe Deep Foam, Vinyl
Cover, High Back, Adjustable
Suspension for Weight/Height,
Fore-Aft Adjustment, Backrest
Tilts and Adjustable Arm
Rests
3 In. Seat Belt with Retractor

Electric Monitor System with
Audible and Visual Warning;
Air Cleaner Restriction
Low Alternator Voltage
indicator
Engine Coolant Temperature
gauge
Engine Oil Pressure
Hydraulic Filter Indicator
Park Brake On-Off Indicator
Seat Belt Indicator
Torque Converter Temperature
gauge
Electric Fuel Gauge,
Illuminated
Electric Hourmeter /
Tachometer/ Voltmeter with
Hydraulic Oil temperature

display, illuminated
Key Start Switch with Electric
Fuel Shut Off
Horn (Conforms to SAE J994,
J1446)
Interior Rearview Mirror
(Conforms to SAE J985)
Hand Throttle
Padded Foot Throttle
Floor Mat
Headliner
Built-In Operator's Manual
Storage Compartment with
Manual
Built-In Beverage and Thermos
Bottle Holder
Coat Hook
LIGHTS (Conforms to SAE J99):
Two Front Driving/Working and
Two Rear Working Halogen
(35,200 Candlepower Each)
Two Front and Two Rear Turn
Signal/ Flashing
Two Rear Stop and Tail
Two Rear Reflectors
Dome Light (Cab)
OVERALL VEHICLE:
Two Front and Two Rear
Built-In Tie Downs
One Piece Unitized
Construction Mainframe
Engine Side Shields with "Tip
Up" Access
1728 (838 Kg.) Standard and
Auxiliary Counterweights
Dent Resistant Rear Fenders
21L - 28 In. 14PR (R4)
Tubeless Rear & 14.5/75-16.1
In. 10 PR (F3) Front Tires
Remote Grease Bank for Front
Axle
Vandal Protection Locking with
Start Switch Key for:
Engine Access Doors
Instrument Panel
70 Gal. (266 L) Fuel Tank:
Wide Mouth Filler Cap
Ground Level Fueling
Built in Water Strainer
Sump with Drain
Reverse Warning Alarm
Switchable to 97 DBA or 111
DBA (Conforms to SAE J994,
J1446)
Exterior Toolbox Located in
Right Stop and Lockable with

(Subject To Change Without Notice)

UTILITY PRODUCTS

710G BACKHOE LOADER

Continued

Start Switch Key	Front Halogen Work lights	Independent Hydraulic
ELECTRICAL:	Pre-wired for Rotating Beacon	Reservoir
12 Volt System	By-Pass Start Safety Cover on	10 Micron Spin-On Replaceable
65 Amp Alternator	Starter	Element
Blade Type Multi-Fused	Positive Terminal Battery	*O" Ring Face Seal Connectors
Circuits	Covers	Circuit Relief Valve
Two Batteries with 380 Min.	HYDRAULICS:	Protection
Reserve Capacity and 1900 CCA	Engine Mounted Piston Pump	
Pre-wired for Two Additional	(Closed Center)	

CODE	DESCRIPTION	LIST PRICE
		US \$

Select One Code From Each Required Category

BASE MACHINE

& UPDATED 27JUN03

1780T	710G BACKHOE LOADER	135,368.00
-------	---------------------	------------

(ROPS)/(FOPS) CANOPY OR CAB

2025	(ROPS)/(FOPS) Canopy NOTE: * Includes molded roof, 2 in. retractable seat belt, floor mat, headliner, two front halogen driving/work lights, two rear halogen work lights, 35,200 candle power each, two front and two rear turn signal/flasher lights, two rear stop and tail lights, two rear reflectors.	In Base Price
2075	Cab with Dual Doors NOTE * Includes safety glass, molded roof, deluxe interior trim, 2 in. retractable seat belt, 4-speed 40,000 BTU fresh air intake heater, defroster and pressurizer, two front halogen driving/work lights, two rear halogen lights 35,200 candle power each, two rear stop and tail lights, two rear reflectors, (2) front two-speed wipers and washer, (1) rear one-speed wiper and 85 amp alternator. Pre-wired for radio.	6,525.00
2085	Cab with Dual Doors and Air Conditioning NOTE * Same as Code 2075 plus 4-speed 27,000 BTU air conditioner. * CFC free R134a * Conforms to SAE J1503 * Includes 95-amp alternator.	8,628.00

(Subject To Change Without Notice)

UTILITY PRODUCTS

710G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
------	-------------	---------------------

SEAT

Continued

2625	Mechanical Suspension Deluxe, Vinyl, Swivel Seat with Lumbar Adjustment and Arm Rests, Fully Adjustable NOTE: * Includes 2-in. retractable seat belt.	In Base Price
2675	Mechanical Suspension Deluxe, Fabric, Swivel Seat with Lumbar Adjustment and Arm Rests, Fully Adjustable NOTE: * Recommended for use with Code 2075 or 2085 Cab. * Includes 2-in. retractable seat belt.	No Charge
2685	Air Suspension Deluxe, Fabric, Swivel Seat with Lumbar Adjustment and Arm Rests, Fully Adjustable NOTE: * Includes 2-inch retractable seat belt. * Recommended for use with code 2075 or 2085 Cab. * Requires code 9055, Tilt Steering Wheel.	112.00

FRONT AXLES

3035	Two Wheel Drive	In Base Price
3085	Four Wheel Drive NOTE: * Includes drive shaft guard.	9,895.00

TIRES AND WHEELS (FRONT AND REAR)

FOR USE WITH 2WD FRONT AXLE (CODE 3025):		
4385	Goodyear 21L - 28 In. 16 PR (R4) Tubeless Rear & 14.5/75-16.1 In. 10 PR (F3) Front Tires NOTE: * Requires Code 3035, Std. Front Axle, 90.5 in. (2.29m) overall tread width.	In Base Price
4425	Goodyear 21L-28 In. 14 PR (R4) Tubeless Rear & 16.5L-16.1 In. 10 PR (H1) Front Tires NOTE: * Requires Code 3035, Std. Front Axle, 89.5 in. (2.26m) overall tread width.	380.00
FOR USE WITH 4WD AXLE (CODE 3075):		
4845	Goodyear 20.5 - 25 In. 12 PR (L2) Tubeless Rear & 15 - 19.5 In. 8 PR Traction Front Sure Grip Lug Tires NOTE: * Requires Code 3085 FWD Axle, 94 in. (2.38 m) overall tread width.	2,045.00
4915	Goodyear 21L - 28 In. 14 PR (R4) Tubeless Rear & 15 - 19.5 In. 8 PR Traction Front Sure Grip Lug Tires NOTE: * Requires Code 3085 FWD Axle, 89.5 in. (2.26 m) overall tread width.	774.00
4916	Firestone 21L - 28 In. 14 PR (R4) Tubeless Rear & 15 - 19.5 In. 8 PR Traction Front Sure Grip Lug Tires NOTE: * Requires Code 3085 FWD Axle, 89.5 in. (2.26 m) overall tread width.	408.00

BACKHOE

(Subject To Change Without Notice)

UTILITY PRODUCTS

710G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
	BACKHOE	

Continued

5025	Standard Dipperstick	In Base Price
------	----------------------	---------------

5075	Extendible Dipperstick	7,875.00
------	------------------------	----------

NOTE:

- * Cannot be used with code 5110, 4 function valve.
- * Requires code 8490 counterweight

USE WITH
5120

BACKHOE VALVES

NOTE:

Refer to DMAC for complete information when installing hydraulic backhoe attachments.

5110	Four Function Valve	In Base Price
------	---------------------	---------------

NOTE:

- * Requires Code 5025, Standard Dipperstick.

5120	Five Function Control Valve	12.00
------	-----------------------------	-------

NOTE:

- * Requires Code 5025, Standard Dipperstick, fifth valve section can operate.
- Field Installed extendible dipperstick

OR

Thumbs, swingers or jaw buckets

- * Fifth valve section with work ports plugged, without circuit reliefs, with right pedal.

- * If Equipped with 5075, Extendible Dipperstick, fifth valve section operates extendible dipperstick.

USE WITH
5075

412.00

5130	Six Function Manual Control Valve	2,009.00
------	-----------------------------------	----------

NOTE:

- * Includes fifth and sixth valve section with work ports plugged without circuit reliefs. Includes left pedal.
- * Also order Attachment Hydraulic Plumbing Kit for Thumb, Clamp, Swinger or Jaw Bucket.
- * If equipped with code 5025, Standard Dipperstick, fifth and/or sixth valve section operates cylinder actuated attachments.
- * If equipped with code 5075, Extendible Dipperstick:
 - Fifth valve section operates extendible dipperstick.
 - Sixth valve section operates cylinder actuated attachments.

BACKHOE CONTROLS

5225	Deere Two Lever Controls (Standard Backhoe or Extendible Dipperstick)	In Base Price
------	---	---------------

NOTE:

- * Includes all Controls.

5286	Deere Backhoe Pattern 2-Lever Pilot Controls (×UPDATED 21JUL03)	1,502.00
------	---	----------

NOTE:

- * Includes all Controls and for Pattern Selection requires Pattern Select Valve Field Kit - CAN NOT swap lines.
- * Recommend tilt steering for greater ease of operation.

BACKHOE AUXILIARY PLUMBING

5310	Less Backhoe Auxiliary Plumbing	In Base Price
------	---------------------------------	---------------

(Subject To Change Without Notice)

UTILITY PRODUCTS

710G BACKHOE LOADER

Continued

CODE DESCRIPTION LIST PRICE US \$

BACKHOE AUXILIARY PLUMBING

Continued

5330	Standard Dipperstick Auxiliary Plumbing NOTE: * Requires Code 5025, Standard Dipperstick and Code 9067, Flow Control Valve. * Includes hydraulic lines from the selective flow valve section to end of dipperstick. * Required for hammers, compactors, high or low flow motor attachments mounted to end of dipperstick.	1,166.00
5350	Extendible Dipperstick Auxiliary Plumbing NOTE: * Requires Code 5075, Extendible Dipperstick and Code 9067, Flow Control Valve. * Includes hydraulic lines from the selective flow valve section to end of dipperstick. * Required for hammers, compactors, high or low flow motor attachments mounted to end of dipperstick.	1,376.00

BACKHOE BUCKETS

5600	Less Backhoe Bucket with Bucket Pins	In Base Price
5696	24" (610 mm) Wide - HD - 11.0 Cu. Ft. Capacity	2,254.00
5736	30" (762 mm) Wide - HD - 14.5 Cu. Ft. Capacity	2,381.00
5776	36" (914 mm) Wide - HD - 18.0 Cu. Ft. Capacity	2,713.00

LOADER

7025	Loader with Return-to-Dig and Two Function Hydraulics (Single Lever)	In Base Price
7075	Loader with Return-to-Dig and Auxiliary Hydraulic Circuit with Dual Lever NOTE: * For M.P. bucket and front attachments includes .50 in. (12.7 mm) hoses and steel lines to loader cross-tube. Includes valve with circuit relief.	1,577.00

option #5

LOADER BUCKETS

7600	Less Loader Bucket with Pins	In Base Price
7675	1.62 Cu. Yd. (1.24 Cu. M.) Bucket with Auxiliary Cutting Edge, Skid Plates and Two Lift Loops NOTE: * 92 in. (2.44 M) Wide. * Includes T126774, .625 x 8 in. (16 x 203 mm) Reversible Bolt-On Cutting Edge with Skid Plates and two built-in lift loops.	3,273.00
7680	1.87 Cu. Yd. (1.43 Cu. M.) Bucket with Auxiliary Cutting Edge, Skid Plates and Two Lift Loops NOTE: * 96 in. (2.44 m) wide * Includes T126774, .625 x 8 in. (16 x 203 mm) Reversible Bolt-On Cutting Edge with Skid Plates and two built-in lift loops.	3,991.00

(Subject To Change Without Notice)

UTILITY PRODUCTS

710G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
------	-------------	---------------------

LOADER BUCKETS

Continued

7685	1,375 Cu. Yd. (1.00 Cu. M.) Multi-Purpose Bucket - 96 In. (2.44 M) Bucket Width with Two Lift Loops NOTE: * 96-in. (2.44 m) wide. * Pre-Punched for (8) tooth shanks OR T126774 Reversible Bolt-On Cutting Edge. * Two built-in lift loops. * Requires Code 7075, Three Function Hydraulics.	5,581.00
------	---	----------

FRONT COUNTERWEIGHT

8480	930 lbs. (419 kg.) Counterweight	983.00
8490	1630 lbs. (734 kg.) Counterweight NOTE: * Recommended for extended backhoe, and standard backhoe with aux. hydraulics.	1,287.00

SPECIAL EQUIPMENT - ORDER AS DESIRED

MISCELLANEOUS:

9045	Chrome Exhaust Extension	118.00
9055	Tilt Steering	425.00
9090	95 Amp Alternator NOTE: * Required with Code 9065, Additional Cab Lights. * Not required if equipped with Code 2085 Cab with Air.	62.00
9065	Deluxe Lighting Package NOTE: * Additional two (2) front, (2) rear additional Halogen Work Lights and (2) side docking lights for Cab * 35,200 candlepower each. * Requires Code 9090, 95 Amp Alternator, except when ordered with Code 2085, Cab with Air.	285.00
9067	Selective Flow Solenoid Valve NOTE: * Requires Code 5330 or 5350 valving.	2,641.00
9070	AM/FM Stereo, Weather Band Radio NOTE: * Includes clock, speakers and special headliner. Radio cannot be used in Europe, Japan or Australia. * Requires Code 2075 or 2085 Cab.	531.00
9075	Cooling System Baffles for High Ambient Temperatures Above 115 Degrees F.	178.00
9080	Engine Coolant Heater NOTE: * Recommended below 32 degrees F, 0 degrees C.	110.00
9085	Electric Ether Starting Aid NOTE: * Recommended below 32 degrees F, 0 degrees C.	141.00

(Subject To Change Without Notice)

UTILITY PRODUCTS

U-5-710G-7

710G BACKHOE LOADER

Continued

CODE	DESCRIPTION	LIST PRICE US \$
9092	Jump Post Start Aid	10.00
9110	Ride Control	998.00
9225	3 In. Retractable Seat Belt	75.00
9460	Spanish Trademarks and Decals	No Charge
9470	French Trademarks and Decals	No Charge

DEALER-INSTALLED ATTACHMENTS

NOTE:

- * The following items can be installed by the Dealer, or contact JRB Custom Works for pricing and installation prior to shipping complete unit from the Dubuque Factory.
- * Prices listed below are for kit material only.

AT188049	LOADER BUCKETS: 1.82 Cu. Yd. (1.24 Cu. M.) Bucket with Auxiliary Cutting Edge and Skid Plates NOTE: * 92 in. (2.44 m) wide. * Includes T126774, .625 x 8-in. (16 x 203 mm) Reversible Bolt-On Cutting Edge with Skid Plates and two built-in lift loops.	3,004.00
AT188048	1.87 Cu. Yd. (1.43 Cu. M.) with Auxiliary Cutting Edge and Skid Plates NOTE: * 96-in. (2.44 M) wide. * Includes T126774, .625 x 8-in. (16 x 203 mm) * Reversible Bolt-On Cutting Edge with Skid Plates. * Includes two built-in lift loops.	3,864.00
AT188053	1.375 Cu. Yd. (1.0 Cu. M.) Multi-Purpose Bucket; 96 In. (2.44 M) Wide NOTE: * 96-in. (2.44 m) wide. * Pre-punched for eight tooth shanks or T126774 Reversible Bolt-On Cutting Edge. * Two built-in lift loops. * Requires Code 7075.	6,221.00
AT183048	BACKHOE BUCKETS: 18 in. (457 mm) Heavy-Duty Bucket	2,027.00
AT183050	24 in. (610 mm) Heavy-Duty Bucket	2,254.00
AT183053	30 in. (762 mm) Heavy-Duty Bucket	2,381.00
AT183056	36 in. (914 mm) Heavy-Duty Bucket	2,586.00
AT183049	18 in. (457 mm) Severe-Duty Bucket	2,694.00
AT183052	24 in. (610 mm) Severe-Duty Bucket	3,010.00
AT183055	30 in. (762 mm) Severe-Duty Bucket	3,438.00
AT183058	36 in. (914 mm) Severe-Duty Bucket	3,887.00

HYDRAULICS:

01 January 2003

US

#3

B. Rear: Manufacturer's standard R4 tread.

MANUFACTURER: DEERE/CAT/
TEREX - GOOD YEAR, NH - GOOD
YEAR OR ARMSTRONG

SIZE AND DESIGNATION: DEERE
- 16.9-24, NH/CAT - 19.5L-24,
TEREX - 16.9-28

80. PAINT: Manufacturer's standard paint and color, factory painted.

90. CONDITIONS:

- A. At a minimum, the Manufacturer's standard warranty for state and municipalities shall be provided. A copy of the warranty shall be provided with the bid.
- B. The Contractor shall provide any and all non-specified features or components necessary in order to provide a complete unit.
- C. See GENERAL SPECIFICATIONS All Construction/Industrial Equipment (GSCI-1).

760-960-110
 (66)

MAKE JOHN DEERE

CONTRACTOR	MODEL	*DISCOUNT F.O.B. CONTRACTOR	PRICE
<u>NORTRAX EQUIPMENT</u>	<u>310G</u>	<u>\$260.00</u>	<u>\$32,939.89 (25)</u>

1. Percentage discount off Manufacturer's current published retail prices for non-specified Options for a State of Florida Base Unit and any Optional models bid. (The percentage discount is applied to the Manufacturer's current published retail prices.)

50% Discount

**Date of current published retail price book: 05/08/02

*Discount for pickup by ordering agency at Contractor's place of business.

**NOTE: ALL DATES MUST BE FOR THE CURRENT PUBLISHED RETAIL PRICE BOOK.

Approximate delivery time required after receipt of order: 45-60 DAYS

OPTION CODING: 760-960-111-Option Number, Tractor-Loader-Backhoe, Industrial, 62 HP, Spec. 66

OPTIONS:

- (1) 1001. High efficiency bypass oil purification system. This system is designed to reduce or eliminate engine oil changes and extend its useful life. The Puradyn Oil Filtration System or approved equivalent. Puradyn Filter Technologies, Inc. 1-800-488-0577.

PRICE: \$758.35



For: Lee County Utilities
Interstate Trailers 70LBG, Fifth Wheel, 35 Ton Capacity
Commodity Code 070-780-030
Florida State Term Contract Number 760-001-03-1
Expires: May 31, 2004

A. Base Unit Price per State Contract Specifications: \$ 26,247.26
Includes: 25' Deck Length
8'-6" Deck Width
3' Beavertail with Steel Treadplate and Traction Bars
3' X 8' Hydraulic Rear Ramps, Self Contained
235/75R17.5, 16 Ply Tires
Hutch H9700 Multi-point Spring Suspension
Air Brakes with Anti-Lock System
2" Nominal Hardwood Decking
D rings every 4'
One Year Standard Manufacturer's Warranty

B. Options Priced On Contract: (Net Prices)

7001 Spare Wheel and Tire	\$ 390.00
8001 Special Color Paint	\$ 275.00
9901 Upgrade to 40 Ton Capacity Model 80LBG	\$ 550.00

C. Additional Contract Options: 14% off current manufacturer's list price
*** See Dealer for additional options that might be available

D. Additional Non-Contract Options:
*** See Dealer for additional options that might be available

*** Prices include freight and delivery.

Direct Purchase Orders To:
Bob Rainey, Governmental Sales Mgr.
Nortrax Equipment Co. SE LLC
5102 North 56th Street, Tampa, FL 33610
Phone (813) 621-4902 Fax (813) 621-8280 Cell (813) 690-8698

Construction/Industrial Equipment and Forklifts

760-001-03-1

Effective: 10/30/2002 through 5/31/2004

Certification

Legal Information

Exhibit A - General Specifications

Exhibit B - Price Sheets

Ordering Instructions

Sample Purchase Order

Revisions

Complete Contract

070-780-030

MAKE INTERSTATE

CONTRACTOR	MODEL	*DISCOUNT F.O.B. CONTRACTOR	PRICE
<u>NORTRAX EQUIPMENT</u>	<u>70LBG</u>	<u>\$260.00</u>	<u>\$26,247.26 (3)</u>

1. Percentage discount off Manufacturer's current published retail prices for non-specified Options for a State of Florida Base Unit and any Optional models bid. (The percentage discount is applied to the Manufacturer's current published retail prices.)

14% Discount

**Date of current published retail price book: 02/01/98

*Discount for pickup by ordering agency at Contractor's place of business.

**NOTE: ALL DATES MUST BE FOR THE CURRENT PUBLISHED RETAIL PRICE BOOK.
Approximate delivery time required after receipt of order: 90-120 DAYS

OPTION CODING: 070-780-031- Option Number, low bed trailer, 35-ton capacity

OPTIONS:

(1) 7001. Spare tire and wheel, mounted and inflated.

(BASE) PRICE: \$390.00
(OPT 9901) PRICE: \$390.00

(2) 8001. Special state color, DOT Yellow, Federal Yellow No. 13538, DuPont #L9069A, ACME No. 2712, Deere No. PT102, or approved equivalent, (may be Contractor painted if factory painting is not available). NOTE: The entire unit, including Options, shall be painted the same color.

(BASE) PRICE: \$275.00
(OPT 9901) PRICE: \$275.00

(3) 9901. Tandem axle, 80,000 pounds net load capacity trailer. Unit shall be of the same Manufacturer. Model bid shall meet or exceed all other minimum requirements and features as specified for the base model bid. Frame structure, axles, suspension and tires shall be sized to carry the maximum net load. Note to bidder: Provide only a price difference between the base model and model bid.

MODEL: 80LBG

PRICE: \$550.00



**Quotation for Lee County Utilities Department
Interstate 14RBS Tag-Along Trailer**

Date: June 30, 2003

Nortrax Equipment Co. is pleased to quote you the following equipment:

One NEW 2003 Interstate 14RBS Tag-Along Equipment Trailer

Includes: All standard equipment and features such as:

- 14,000 lb. Capacity
- 17'-10" Deck Length
- 32" Dovetail
- Two 8,000 lb. Heavy Duty Axles
- Four 215/75R X17.5 – 16PR Radials
- Heavy Duty Electric Brakes
- 2" Hardwood Decking
- Adjustable Pintle Eye Hitch
- 12,000 lb. Screw Type Jack
- Standard Grey Paint

Total Price including all options:

\$ 6,990.00

FOB Lee County, FL Fleet Management Division

Allow 60 days for delivery

*** For use with John Deere 50CZTS Mini-Excavator

Direct Purchase Orders To:

Eny Sanchez, Governmental Sales

Nortrax Equipment Co. SE LLC

4343 N.W. 76th Avenue, Miami, FL 33166

Ph: (305) 592-5740 X-224 Fax: (305) 513-4353 Cell: (305) 586-2921



**Quotation for Lee County Utilities Department
Interstate 14RBS Tag-Along Trailer**

Date: June 30, 2003

Nortrax Equipment Co. is pleased to quote you the following equipment:

One NEW 2003 Interstate 14RBS Tag-Along Equipment Trailer

Includes: All standard equipment and features such as:

- 14,000 lb. Capacity
- 17'-10" Deck Length
- 32" Dovetail
- Two 8,000 lb. Heavy Duty Axles
- Four 215/75R X17.5 – 16PR Radials
- Heavy Duty Electric Brakes
- 2" Hardwood Decking
- Adjustable Pintle Eye Hitch
- 12,000 lb. Screw Type Jack
- Standard Grey Paint

Total Price including all options:

\$ 6,990.00

FOB Lee County, FL Fleet Management Division

Allow 60 days for delivery

*** For use with John Deere 50CZTS Mini-Excavator

Direct Purchase Orders To:

Eny Sanchez, Governmental Sales

Nortrax Equipment Co. SE LLC

4343 N.W. 76th Avenue, Miami, FL 33166

Ph: (305) 592-5740 X-224 Fax: (305) 513-4353 Cell: (305) 586-2921



**Quotation for Lee County Utilities Department
Interstate 20DT Trailer**

Date: June 30, 2003

Nortrax Equipment Co. is pleased to quote you the following equipment:

One NEW 2003 Interstate 20DT Dual Axle Equipment Trailer

Includes: All standard equipment and features such as:

- 20,000 lb. Capacity
- 19'-0" Deck Length
- 5'-0" Dovetail
- Two 10,000 lb. Heavy Duty Axles
- Four 235/85R X 16 LRE Tires
- Heavy Duty Electric Brakes
- 2" Hardwood Decking
- Adjustable Pintle Eye Hitch
- 12,000 lb. Drop Leg Jack
- Standard Grey Paint

Total Price including all options:

\$ 8,499.00

FOB Lee County, FL Fleet Management Division

Allow 60 days for delivery

*** For use with John Deere 410G Backhoe Loader

Direct Purchase Orders To:

Eny Sanchez, Governmental Sales

Nortrax Equipment Co. SE LLC

4343 N.W. 76th Avenue, Miami, FL 33166

Ph: (305) 592-5740 X-224 Fax: (305) 513-4353 Cell: (305) 586-2921



**Quotation for Lee County Utilities Department
Interstate 40DLA Trailer**

Date: June 30, 2003

Nortrax Equipment Co. is pleased to quote you the following equipment:

One NEW 2003 Interstate 40DLA Dual Axle Equipment Trailer

Includes: All standard equipment and features such as:

- 40,000 lb. Capacity
- 19'-0" Deck Length
- 5'-0" Dovetail
- Two 22,500 lb. Heavy Duty Axles
- Eight 215/75R X 17.5 16 Ply Radials
- Heavy Duty ABS Brakes
- 2" Hardwood Decking
- Adjustable Pintle Eye Hitch
- 12,000 lb. Drop Leg Jack
- Standard Grey Paint

Total Price including all options:

FOB Lee County, FL Fleet Management Division

Allow 60 days for delivery

\$ 14,795.00

*** For use with John Deere 710G Backhoe Loader

**Direct Purchase Orders To:
Eny Sanchez, Governmental Sales
Nortrax Equipment Co. SE LLC**

4343 N.W. 76th Avenue, Miami, FL 33166

Ph: (305) 592-5740 X-224 Fax: (305) 513-4353 Cell: (305) 586-2921

**MEMORANDUM
FROM
THE DIVISION OF PURCHASING**

DATE: July 29, 2003

TO: KRISTIE KROSLACK
COUNTY ATTORNEY'S OFFICE

Ep for JK
FROM: JANET SHEEHAN, CPPB
PURCHASING DIRECTOR

RE: BLUE SHEET # 20030893

PROJECT: John Deere Equipment

TYPE: Project # EX030641

AWARDED TO: Nortrax Equipment Company

If there are any questions or concerns with this package, please contact Chevone Peterson at 689.7385.