



SECTION A-A

- ① LIMITS OF PAVEMENT
- ② EXTEND CASING 4' MIN. BEYAND E.O.P. AND/OR BACK OF CURB FOR L.C.D.O.T. MAINTAINED R.O.W. AND 8' MIN. FOR F.D.O.T. MAINTAINED R.O.W.
- ③ STEEL CASING PIPE CONFORMING TO ASTM A-139
- ④ 7' O.C. MAX OR AS PER MANUFACTURER'S RECCOMENDATION
- ⑤ L.C.U. APPROVED CASING SPACERS
- ⑥ SEAL CASING ENDS WITH: 8" WALL OF BRICK MASONRY WITH WEEP HOLE INSTALLED NEAR BOTTOM, OR APPROVED EQUAL
- ⑦ ALL JOINTS OF THE CARRIER PIPE SHALL HAVE BELL RESTRAINTS
- ⑧ 10 GAUGE DOUBLE INSULATED COPPER WIRE (SEE LCU STANDARD DETAIL G-03)



LEE COUNTY
UTILITIES
ENGINEERING

1500 MONROE STREET
FORT MYERS, FLORIDA 33901

TITLE:

JACK AND BORE

REVISION:

1/29/24

DETAIL NO:

G-06.dwg

NOT TO SCALE